

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-30168-00-00  
Spot: NENENE Sec/Twnshp/Rge: 19-9S-20W  
4950 feet from S Section Line, 330 feet from E Section Line  
Lease Name: J.L. BALTHAZOR Well #: 6  
County: ROOKS Total Vertical Depth: 3820 feet

Operator License No.: 5364  
Op Name: BEREN CORPORATION  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3802		150 SX
SURF	8.625	242		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/07/2015 12:00 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: BOB GRANT Company: BEREXCO LLC Phone: (316) 772-8160

Proposed Production: Open hole 3802' - 3820'.  
Plugging Casing leaks: 1735' - 1767'.  
Method: No upper cement records. Need to perforate 2 holes each at 2250' and 1125'.  
  
Ordered 350 sx 60/40 pozmix 4% gel cement, 1300 # gel and 500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/07/2015 4:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Perforated 2 holes each at 2250' and 1125'. Ran tubing to 3787'. Quality Well Service pumped 1300# gel followed by 25 sx cement w/100 # hulls. Pulled tubing to 2284' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 1035' and pumped 120 sx cement w/200 # hulls. Cement circulated. Pulled tubing out of hole. Topped off 5 1/2" casing w/15 sx cement. Casing. Full. Hooked up to backside and pumped 50 sx cement. Maximum pressure 100 psi. Shut in pressure 100 psi.

Remarks: QUALITY WELL SERVICE TICKET # 6440

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

DEC 09 2015

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 21 2015  
CONSERVATION DIVISION  
WICHITA, KS

700  
12-30-15