

1 030666

To:

API NUMBER 15- N/A

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE SW, SEC. 36, T 24 S, R 15 (W/F)

TECHNICIAN'S PLUGGING REPORT

Operator License # 6123

Operator: Chase Well Service

Name & Address P. O. Box 355

Great Bend, KS 67530

990 feet from S section line

2970 feet from E section line

Lease Name Thurow "A" Well # 3

County Stafford

146.71

Well Total Depth 4514 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 283

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Chase Well Service License Number 6123

Address P. O. Box 355, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 28 Month: February Year: 19 86

Plugging proposal received from Kenny Link

(company name) Chase Well Service (phone) 316-793-9556

were: 5 1/2" at 4405' 4 1/2" liner at 4514' Perfs at 4502-06'; 4461-65'; 4441-47'; 4428-32'
Casing parted at 1080' - Milled outside pipe - abandoned work-over. Pumped through tubing -
then swedged into 5 1/2" casing.

1st plug at 800' with 30 sx cement 2nd plug at 500' with 30 sx cement

3rd plug at 200' with 30 sx cement 4th plug pump 50 sx cement down backside.

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:25 pm Day: 28 Month: February Year: 19 86

ACTUAL PLUGGING REPORT Pumped through tubing - 1st plug at 800' with 30 sx cement, 2nd
plug at 500' with 30 sx cement, 3rd plug at 200' with 30 sx cement, 4th plug swedged into
5 1/2" and pumped 50 sx cement. Cement circulated up backside and fell down 180'. Let
set one hour and pumped with 40 sx cement. Cement circulated. Set 1 hour and pumped 10
sx cement down annulus at 300 psi. Cement set up in casing.

Remarks: No recovery. Used 60/40 Pozmix 6% gel 2% cc by Halliburton.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSIONSigned Steve Durrant
(TECHNICIAN)

DATE MAR 04 1986

INV. NO. 12842 2-28

MAR 4 1986
3-4-86 Rec'd
CONSERVATION DIVISIONFORM CP-2/3
Rev. 01-84