

1120903

3-24

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,954-0000

W/2 SW NW, SEC. 26, T 24 S, R 15 W/4

3300 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Piland Well # 1-26

Operator: F.G. Holl Company L.L.C.

County Stafford

Name & Address P.O. Box 780167

Well Total Depth 4515 146.73 feet

Wichita, KS 67278-0167

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 323

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Sterling Drilling Company License Number 5142

Address P.O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 4:30 p.m. Day: 24 Month: 3 Year: 19 94

Plugging proposal received from Vaughn Thompson

(company name) Sterling Drilling Company (phone) 316-278-2131

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1000' with 50 sx cement,

2nd plug at 360' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6 p.m. Day: 24 Month: 3 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 1000' with 50 sx cement,

2nd plug at 360' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAR 28 1994

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

3-28-94 CONSERVATION DIVISION

(If additional description is necessary, use BACK of this form, Kansas

INVOICED

observe this plugging.

DATE 4-6-94

Signed Duane Rankin (TECHNICIAN)

INV. NO. 40221

EFFECTIVE DATE: 3-8-94

State of Kansas

NOTICE OF INTENTION TO DRILL 185-22,954

FORM MUST BE TYPED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date April 1, 1994
month day year

Spot W/2 SW NW Sec 26 Twp 24 S. Rg 15W East West

OPERATOR: License # 5056
Name: F. G. Holl Company L.L.C.
Address: 6427 E Kellogg P.O. Box 780167
City/State/Zip: Wichita, Ks 67278-0167
Contact Person: Elwyn H. Nagel
Phone: (316) 684-8481

3300' FSL feet from South / North line of Section
4950' FEL feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Stafford
Lease Name: PILAND Well #: 1-26
Field Name: Farmington

CONTRACTOR: License #: 5142
Name: Sterling Drilling Company

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Kinderhook Sand, Mississippi
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2020 est. feet Hgt
Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 300'
Depth to bottom of usable water: 300'
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 320'
Length of Conductor pipe required: NA
Projected Total Depth: 4450'
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations: X well farm pond other

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec X Infield X Mud Rotary
X Gas ... Storage ... Pool Ext. ... Air Rotary
... OWSO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other
If OWSO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth: _____
Bottom Hole Location: _____
Exp. 9/3/94

OUR Permit # (Applied for by Sterling Drlg.)
Will Cores Be Taken? yes X no
If yes, proposed zone: _____

320' Alt. I Reg RECEIVED
KANSAS CORPORATION COMMISSION

AFFIDAVIT

Pusher Wynne Thompson
SPUD DATE 3-17-94 INIT. WHP
LENGTH SURFACE PLANNED 320'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 7 7/8 @ 323 CONDUCTOR
ANHYDRITE T- B ELEVATION
still dry
TD 4515 FORMATION Arbuckle
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ if found Ft. W/ 35 SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 1000 Ft. W/ 50 SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 360 Ft. W/ 50 SX
40' Plug @ 10 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 7 SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN DR DATE 3-21-94
TYPE OF CEMENT 60-40-670
STARTING TIME 5:00 AM DATE 3-24-94
COMPLETION TIME 8:00 AM DATE 3-24-94
CEMENT COMPANY Halliburton
Wynne witnessed all