

To: 1 030685
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,650-A ⁻⁰⁰⁰¹
E/2 E/2 NE SEC. 26, T 24 S, R 15 W/EX
3960 feet from S section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5088
Operator: John J. Darrah, Jr.
Name & Address: 412 E. Douglas, Suite One
Wichita, KS 67202

330 feet from E section line
Lease Name Blount OWWO Well # 1
County Stafford 140.08
Well Total Depth 4310 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111
Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 1:00 pm Day: 4 Month: April Year: 19 86

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 4 1/2" at 4287' PBD 4245' Perfs at 4156-62' Pump through 4 1/2" with mud between plugs
1st plug sand back 50' above the perfs and dump 2 sx cement on top of sand through bailer
2nd plug at 850' with 50 sx cement
3rd plug at 330' with 40 sx cement
4th plug at 40' with 10 sx cement filling hole to surface

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 pm Day: 4 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4106' and dumped 2 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls and 120 sx cement with 2 sx hulls and 1/4 flow-seal.

Remarks: Recovered 2100' 4 1/2" casing. Used High Yield Econolite cement by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE APR 15 1986
INV. NO. 13453

RECEIVED
APR 15 1986
4-15-86
CONSERVATION DIVISION

Signed Steve Blount (TECHNICIAN)