

To: 1 052132
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

5-16

API NUMBER 15-185-21,513 - 0000
W/2 E/2 NE, SEC. 15, T 24 S, R 15

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056
Operator: F.G. Holl Company, L.L.C.
Name:
Address: P.O. Box 780167
Wichita, KS 67278-0167

4050 feet from S section line
990 feet from E section line
Lease Name Cummins Well # 3-15
County Stafford 137.80
Well Total Depth 4240 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 16 Month: 5 Year: 1997

Plugging proposal received from Thom Pool

(company name) F.G. Holl Co. (phone) 316-793-0289

logs: 4 1/2" at 4239' w/200 sx cement, PBD 4175', Perfs at 4148-52'

1st plug pump 50 sx cement and 2 sx hulls on bottom,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper

plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 16 Month: 5 Year: 1997

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 50 sx common cement to bottom,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 250 psi.

RECEIVED
MAY 21 1997
5-21-97

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2070' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / observe this plugging.

Signed Richard M. Lacey (TECHNICIAN)

DATE 5-22-97

INV. NO. 48161

5-16 JUL 22 1997