

To: 1 052170
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

9-22

API NUMBER 15- 185-21,159-0000
C SE NE, SEC. 15, T 24 S, R 15 W/E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 5056
Operator: F.G. Holl Company, L.L.C.
Name & Address: P.O. Box 780167
Wichita, KS 67278-0167

Lease Name Cummins Well # 1-15
County Stafford 138.87
Well Total Depth 4273 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9 a.m. Day: 22 Month: 9 Year: 19 97

Plugging proposal received from Kenny Gates
(company name) Pratt Well Service (phone) 316-672-2531

Work: 4 1/2" at 4268' w/250 sx cement, PBTB 4224', Perfs at 4160-64'
1st plug sand back to 4100' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN) Rec'd 9-30-97

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 10 a.m. Day: 22 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4100' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 325 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2005' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

(I and/or ~~XXXXXX~~ observe this plugging.

DATE 9-30-97

Signed Richard W. Lacy (TECHNICIAN)

INV. NO. 49175