

1052274
TO: STATE CORPORATION COMMISSION

7-23

API NUMBER 15-185-23,042-0000
SW SE SW SEC. 18, T 24 S, R 15 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3630 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME YOUNG WELL # 3-18

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD

OPERATOR LICENSE # 5056 WELL TOTAL DEPTH 4485 145.77 FEET

OPERATOR: F.G. HOLL COMPANY LLC PRODUCTION CSG: SIZE 4 1/2 " FEET 4459

NAME AND ADDRESS 6427 E KELLOGG PO BOX 780167 SURFACE CASING: SIZE 8 5/8" FEET 236'

ADDRESS WICHITA, KS 67278-0167

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 E BETH DR, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 23 MONTH: 7 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM ROB LONG

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-278-2476

WERE: PERFS AT 3895 TO 3898, PBTD 4425'

1ST PLUG PUMPED 1 SX HULLS AND 25 SX CEMENT TO 3050'

2ND PLUG AT 1000' WITH 5 SX GEL AND 50 SX CEMENT

3RD PLUG AT 270' WITH 40 SX CEMENT

4TH PLUG AT 40' WITH 10 SX CEMENT

RECEIVED
STATE CORPORATION COMMISSION

7-27-98
7-27-98
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 2:45 PM DAY: 23 MONTH: 7 YEAR: 1998

ACTUAL PLUGGING REPORT 1ST PLUG PUMPED 1 SX HULLS AND 25 SX CEMENT TO 3050'

2ND PLUG AT 1000' WITH 5 SX GEL AND 50 SX CEMENT

3RD PLUG AT 270' WITH 40 SX CEMENT

4TH PLUG AT 40' WITH 10 SX CEMENT

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000' OF 4 1/2" CASING
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED
(DID) OBSERVE THIS PLUGGING.

DATE 7-30-98
INV. NO. 51046

SIGNED Richard M. Lacy
(TECHNICIAN) FORM CP-2/3