

To: 1 120014
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-20,614-0000
SW SW NE, SEC. 23, T 24 S, R 15 W&E
3040 feet from S section line
1990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Suiter Sutor Well # 1

Operator: Murfin Drilling Company
Name &
Address 250 North Water, Suite 300
Wichita, KS 67202

County Stafford 143.81
Well Total Depth 4425 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 4/8 feet 527

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 20 Month: 8 Year: 19 87

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4424' PBD 4170' Perfs at 4110-14'

1st plug pump 1 sx hulls and 25 sx cement,

2nd plug pump 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release

8 5/8" wiper plug and pump 135 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 20 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped bottom with 25 sx cement and 1 sx hulls at 3500',

2nd plug pumped through 8 5/8" surface casing with 200 lbs. hulls, 14 sx gel, 50 lbs.

hulls, 50 sx cement, 6 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped

135 sx cement.

STATE RECEIVED
CONSERVATION DIVISION
Wichita, Kansas
AUG 25 1987
8-25-87

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2700' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

~~INVOICED~~ INVOICED ~~RESERVE~~ RESERVE this plugging.

DATE 8-25-87
INV. NO. 17954

Signed Duane Rankin
(TECHNICIAN)