

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185- 21,936-0000

SE NE NW, Sec. 15, T 24 S, R 15 W/X

990 feet from N/X section line

2310 feet from W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Biggs Well # 1-15

Operator: F. G. Holl
Name & 6427 East Kellogg
Address Wichita, KS 67207

County Stafford

Well Total Depth 4242 feet 137.86

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Sterling Drilling Co. License Number 5142

Address P. O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 4:00 pm Day: 30 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Jim Shriner

(company name) Sterling (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 4020' with 50 sx cement

2nd plug at 970' with 50 sx cement

3rd plug at 300' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement.

Signed Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 pm Day: 30 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4020' with 50 sx cement, 2nd plug at 970' with 50

sx cement, 3rd plug at 300' with 50 sx cement, 4th & 5th plugs solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement.

Remarks: Use 60/40 Pozmix, 2% gel by Halliburton

RECEIVED
STATE CORPORATION COMMISSION
2-2-84
FEB 02 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE 2-3-84

INV. NO. 0042

Signed Paul A. Luthie (TECHNICIAN)