

KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2125
Wichita, KS 67202

API NUMBER: 15-155-01,015 - 0000

12-26-95

SW SW SE SEC 26, T 22 S, R 9W

OPERATOR LICENSE # 30128

330 FEET FROM S SECTION LINE

OPERATOR: Kenneth S. White

2310 FEET FROM E SECTION LINE

NAME & 200 E. 1st, Suite 405

LEASE NAME: Schweizer WELL # 1

ADDRESS: Wichita, KS 67202

COUNTY: Reno

WELL TOTAL DEPTH: 3692' (3665') 119.99

CONDUCTOR PIPE: @

SURFACE CASING: 8 5/8" @ 246'

ABANDONED OIL WELL GAS WELL x INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

RECEIVED
KANSAS CORPORATION COMMISSION

PLUGGING CONTRACTOR Gressel Oilfield Services, Inc.

MAY 23 1996 5-23-96

ADDRESS: PO Box 607, Burrton, KS 67020-0607

LICENSE: 3004

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 22 MONTH: December YEAR: 1995

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING PROPOSAL RECEIVED FROM Kenneth S. White

COMPANY NAME: Kenneth S. White

PHONE: 316-263-4007

WERE: Sand to 3500' and top with 5 sacks cement. Shoot pipe off and pull to 1300'. Spot 35 sacks cement. Pull pipe to 800'. Spot 35 sacks cement. Pull pipe to 300' and circulate cement to the surface. 5 1/2" casing at 3692'. Perforations at 3552' to 3576'

PLUGGING PROPOSAL RECEIVED BY: Steve VanGieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { x }

COMPLETED: HOUR: 14:00 DAY: 26 MONTH: December YEAR: 1995

ACTUAL PLUGGING REPORT: Sat CIBP at 3500' and topped with 2 sacks cement. Shot pipe off at 2239'. Pulled pipe to 1300' and spotted 35 sacks cement. Pulled pipe to 800' and spotted 35 sacks cement. Pulled pipe to 300' and circulated 90 sacks cement to surface. Retrieved 2239' of 5 1/2" casing.

REMARKS: Used 60/40 Pos mix with 4% gel by Allied--Invoice #3749.

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

Michael R. Wilson
Michael R. Wilson AGENT

DATE 5-24-96

FORM CP-2/3
REV. 3/90

INV. NO. 45638

AW