

1 080161

15-151-10057-00-01

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- OWWO

NE SW SE, SEC. 28, T 29 S, R 14 W

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name A & W Farms Well # 1

Operator: Raymond Oil Company, Inc.

County Pratt

Name & Address One Main Place, Suite 900

Well Total Depth 4568 148.46 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 418

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00 pm Day: 7 Month: June Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2 set at 4538' Perfs 4205-10' PBD 4468'

1st plug sand back to 4150 and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by J. M. [Signature]  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 pm Day: 7 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4538' Perfs 4205-10' PBD 4468'

1st plug sanded back to 4150' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack

released 8 5/8" rubber plug and pumped an additional 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 14 1984 06-14-84

Used 60/40 Pozmix 2% gel 3% cc by Sun. They recovered 3599' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed J. M. [Signature]  
(TECHNICIAN)

DATE 6-18-84

INV. NO. 20666  
6-7