

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,405-00-00

NE NE NW, Sec. 27, T 29 S, R 14 W/X

330 feet from N/X section line

2310 feet from W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Kerr Well # 1

Operator: Raymond Oil Company, Inc.
Name & One Main Place, # 900
Address Wichita, KS 67202

County Pratt

Well Total Depth 4679 feet 152.06

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling Co. License Number 5420

Address 5532 West 10th, Great Bend, KS 67530

Company to plug at: Hour: 12:00 pm Day: 23 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Judy Stephens

(company name) White & Ellis (phone) 316-792-2424

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 4600' with 50 sx cement

2nd plug at 790' with 50 sx cement

3rd plug at 390' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement.

6th plug to plug waterwell with 5 sx cement.

7th plug to circulate rathole with 15 sx cement. Signed J. A. Noel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 5:30 pm Day: 23 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4600' with 50 sx cement, 2nd plug at 790' with 50

sx cement, 3rd plug at 390' with 50 sx cement, 4th & 5th plugs solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement. Plug water well with

5 sx cement. Circulate rathole with 15 sx cement.

Remarks: Use 60/40 Pozmix, 2% gel, 3% cc. by Sun Cementing

RECEIVED
STATE CORPORATION COMMISSION

FEB 02 1984

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as hereinafter stated and that I (did / ~~XXXXXX~~) observe this plugging.

Signed J. A. Noel
(TECHNICIAN)

INVOICED
DATE 2-6-84
INV. NO. 0078