

1050427

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE NW NE, SEC. 27, T. 29 S, R. 14 W/XX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,514 - 00 *RO*

TECHNICIAN'S PLUGGING REPORT

4950 feet from S section line
1650 feet from E section line

Operator License # 5399

Lease Name Kerr Well # "E" 1

Operator: American Energies Corporation

County Pratt 152.75

Name & Address 575 Fourth Financial Center

Well Total Depth 4700 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 353

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 E. Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 4:30 am Day: 29 Month: December Year: 19 84

Plugging proposal received from Gary Marshall

(company name) Beredco (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1200' with 50 sx cement

RECEIVED
STATE CORPORATION COMMISSION

2nd plug at 420' with 50 sx cement

3rd plug solid bridge hulls - plug at 40' -- cement to surface with 10 sx cement

JAN 09 1985

5th plug to circulate rat hole with 10 sx cement

CONSERVATION DIVISION
Wichita Kansas

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 am Day: 29 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1200' with 50 sx cement, 2nd plug at 420' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Buie
(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 1-15-85

Signed Richard W. Lacey (TECHNICIAN)

INV NO. 6447