

10-25-15-155-20732-0000

2 070115

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SE, SEC. 2, T 22 S, R 10 W/EX
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3242

Lease Name Sleeper Well # 1

Operator: Commonwealth Petro. Corp.
Name & Address P. O. Box 2458
Hutchinson, KS 67504.

County Reno 120.90

Well Total Depth 3720 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8-5/8 feet 235

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Al Nicholas Casing License Number 6698

Address P. O. Box 108, Geneseo, KS 67444

Company to plug at: Hour: 8:30 Day: 25 Month: 10 Year: 19 88

Plugging proposal received from Al Nicholas

(company name) Nicholas Casing Pullers (phone) 316-824-6467

were: Sand bottom to 3230' 4 sx - pull casing to 1400' 35 sx plug - pull to 900' -
set 35 sx plug - pull to 285' and circulate to surface.

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

10-31-88 OCT 31 1988

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by John Sanders
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 Day: 25 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT Sanded bottom to 3230' and ran 4 sx common with bailer -
pulled 4-1/2" casing to 1400' - pumped a 35 sx plug - pulled to 930' and pumped
a 35 sx plug - pulled casing to 285' - circulated to surface - 85 sx - recovered
2575' of 4-1/2" casing.

Remarks: Pumped by HALLIBURTON 60/40 2% gel #763044
(If additional description is necessary, use BACK of this form.)

INVOICED

(did / did not) observe this plugging.

DATE 11-3-88

WV. NO. 22862
10-25

Signed [Signature]
(TECHNICIAN)