

TO
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20081-00-00
Spot: CW2SENV Sec/Twnshp/Rge: 1-24S-16W
1980 feet from N Section Line, 3630 feet from E Section Line
Lease/Unit Name: REAVES Well Number: 1
County: EDWARDS Total Vertical Depth: 4111 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

Conductor Pipe: Size feet: \$133.61
Surface Casing: Size 8.625 feet: 292 WITH 210 SX CMT
Production: Size 4.5 feet: 4111 WITH 175 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 07/02/2002 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 3980' & 4 SX CMT. 1ST PLUG AT 620' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/02/2002 9:40 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4100'. PERFS AT 4029-35 & 4064-65'. SQUEEZED AT 1470' WITH 100 SX CMT. SANDED TO 3980' & 4 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 620' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
7-19-02
JUL 19 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 620' OF 5 1/2" CASING (PIPE PARTED).

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED

JUL 16 2002

DATE 7-19-02

WEL NO. 2003060065

Form 2/93