

1030319

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,159-0000

SW NE SW, SEC. 1, T 24 S, R 16 W/E

1650 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Rec'd
11-5-84

Operator License # 5258

Lease Name Bright

Operator: Messman-Rinehart Corporation

County Edwards

Name & Address 500 Bitting Building

Well Total Depth 131.85 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:15 am Day: 1 Month: November Year: 19 84

Plugging proposal received from Joe Maize

(company name) Kelso (phone) 316-318-2457

were: 2 7/8" set at 4051' Open Hole

1st plug pump 10 sx cement to bottom and stop plug at 3860'

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Steve Shumout
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 am Day: 1 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 2 7/8" set at 4051' Open Hole

1st plug pumped 10 sx cement to bottom and stopped plug at 3860', 2nd plug squeezed

well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8"

rubber plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in pressure 150 psi.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

(I did / ~~did not~~) observe this plugging.

INVOICED

DATE 11-7-84

Signed Steve Shumout
(TECHNICIAN)

INV. NO. 4653

11-1