

1 080598

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,415-0000
C NW NW, SEC. 11, T 24 S, R 14 W/E
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9740

Lease Name Bookstore Well # 2-11

Operator: Petro Locators, Inc.

County Stafford 137.48

Name & Address P.O. Box 77

Well Total Depth 4230 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 403

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co., Inc. License Number 5929

Address 205 E. Central, Suite 120, Wichita, KS 67202

Company to plug at: Hour: 11 P.m. Day: 11 Month: 2 Year: 19 87

Plugging proposal received from Leonard Williamson

(company name) Duke Drilling Company, Inc. (phone) 316-792-1171

were: to fill hole with heavy mud and spot cement through drill pipe Arbuckle 4207'

1st plug at Arbuckle Top with 25 sx cement, 2nd plug at Base Anhydrite with 50 sx cement,

3rd plug at 30' out base of surface pipe with 50 sx cement, 4th plug at 40-0' with 10

sx cement, 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:30 a.m. Day: 12 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 870' with 50 sx cement,

2nd plug at 433' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If desired, please observe this plugging.)

DATE 2-19-87

INV. NO. 16156

Signed J. A. [Signature]
(TECHNICIAN)

STATE CORPORATION COMMISSION
2-18-87
FEB 18 1987
CONSERVATION DIVISION
Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date February 4, 1987 month day year 3:44

API Number 15- 185-22, 415

OPERATOR: License # 9740 Name PETRO LOCATORS, INC. Address P. O. Box 77 City/State/Zip Pratt, Kansas 67124 Contact Person Clarence Michael Phone 316/672-3040

C. NW NW Sec. 11 Twp. 24 S, Rg. 14 East 4620 Ft. from South Line of Section 4620 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5929 Name DUKE DRILLING CO., INC. City/State Great Bend, Kansas

Nearest lease or unit boundary line 660 feet County Stafford

Lease Name Bookstore Well # 2-11 Ground surface elevation feet MSL

Well Drilled For: Well Class: Type Equipment: X Oil SWD X Infield X Mud Rotary X Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Depth to bottom of fresh water 80 Depth to bottom of usable water 225

Surface pipe by Alternate: 1 X 2 Surface pipe planned to be set 400

Conductor pipe required Projected Total Depth 4200

Formation Arbuckle

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 2/3/87 Signature of Operator or Agent Sally R. Byers Title Agent

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt. This Authorization Expires 2-3-87 Approved By 2-3-87

Handwritten note: Move in 2-3-87 set 400' of 8 1/2" for KCC

C. NW NW Sec. 11 Twp. 24 S, Rg. 14 East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Arbuckle Top feet depth with 50-25 sxs of 60/40 Pozmix, 6% gel
2nd plug @ 900 feet depth with 50 sxs of 60/40 Pozmix, 6% gel
3rd plug @ 430 feet depth with 50 sxs of 60/40 Pozmix, 6% gel
4th plug @ 40 feet depth with 10 sxs of 60/40 Pozmix, 6% gel
5th plug @ feet depth with sxs of
(2) Rathole with 15 sxs (b) Mousehole with sxs

Table with columns: PUSHER, TD, SURFACE PIPE @, ANHYDRITE, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @ FT. W/ SX, 2nd PLUG @ FT. W/ SX, 3rd PLUG @ FT. W/ SX, 4th PLUG @ FT. W/ SX, RAT HOLE CIRCULATED W/ SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY, TECHNICIAN