

To: 1 120552  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-9 185-21,181-A 0001 2300  
API NUMBER 19-  
NE SE NE, SEC. 10, T 24 S, R 14 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 9324

Operator: JFW Inc.  
Name & Address: RR 1, Box 26  
Plevna, KS 67568

3630 feet from S section line  
330 feet from E section line

Lease Name Bartlett Well # 1

County Stafford 138.32

Well Total Depth 4256 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 401

Abandoned Oil Well Gas Well Input Well SWD Well D&A X  
Never produced

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 9 Month: 4 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4250', Perfs at 4075-80'

1st plug sand back to 4025' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
4-16-91  
APR 16 1991

Plugging Proposal Received by Steve Pfeifer CONSERVATION DIVISION  
(TECHNICIAN) Wichita, Kansas

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 p.m. Day: 9 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4025' and dumped 5 sx cement  
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-600 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
I hereby acknowledge and observe this plugging.

DATE 4-22-91

INV. NO. 31634

Signed [Signature] (TECHNICIAN)