

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH.

**Locate well correctly on above
Section Plat**

Stafford

County. Sec. 9 Twp. 24S Rge. 13 (E) 13 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 330' N & 330' W of SE Corner

Lease Owner.....Continental Oil Company

Lease Name Jo Holmes

Well No. 1

Office Address Box 1267, Ponca City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole)..... **Dry hole**

Date well completed..... 12/16 19 41

Application for plugging filed 12/16 19. 41

Application for plugging approved..... 12/18 19. 41

Plugging commenced..... 12/18/41 41
18/18 19 13

Plugging completed..... 12/18 1941

Reason for abandonment of well or producing formation.....No production

If a producing well is abandoned, date of last production.....None.....19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. T. Alexander, Great Bend, Kansas

Producing formation Arbuckle Lime Depth to top 4081' Bottom 4116' Total Depth of Well 4116' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

The hole was filled with heavy mud to within 440' of the top, a wood plug was set at this depth and cemented with 10 sacks of cement, the hole was then filled to within 38' of the top with heavy mud and a wood plug was set at this depth and cemented with 10 sacks of cement bringing the cement plug to within 8' of the top, the hole was then filled with heavy mud to the top and the 10-3/4" OD casing welded over with a steel plate or cap.

The 440' of 10-3/4"OD casing left in this well was set at 437' and cemented with 400 sacks of cement.

Note: All of the above footages are calculated from the ground level.

PLACING
FILE 9-243-13W
BOOK PAGE 19 LINE 19

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Continental Oil Company, c/o F. L. Dunn
Address R. F. D. #4, Lyons, Kansas

STATE OF Kansas COUNTY OF Rice ss

F. L. Dunn.....(employee of owner) or (~~owner-operator~~) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

R. F. D. #4, Lyons, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of January 1942

My commission expires.

October 21, 1944

Notary Public.

JO HOLMES NO. 1

Spudded: November 25, 1941
 Drlg. Completed: December 16, 1941
 Date Plugged: December 18, 1941

Loc: 330' N & 330' W of SE Corner
 of Sec. 9, Twp. 24S, Rge. 13W,
 Stafford County, Kansas

From	To	Formation	From	To	Formation
0	80	Sand	2835	2880	Shale & shells
80	187	Clay & gravel	2880	2897	Sand & lime
187	444	Shale & shells	2897	2915	Lime & shale
444	552	Red bed	2915	3060	Shale & shells
552	748	Shale & shells	3060	3100	Shale
748	780	Anhydrite	3100	3185	Lime
780	1320	Shale & shells	3185	3280	Lime & shale
1320	1350	Salt	3280	3345	Shale & lime
1350	1620	Shale & shells	3345	3455	Lime
1620	1820	Lime	3455	3505	Shale
1820	1980	Lime & shale	3505	3535	Shale & shells
1980	1990	Shale	3535	3611	Lime
1990	2050	Shale & shells	3611	3620	Break shale
2050	2080	Sand	3620	3865	Lime
2080	2130	Broken lime	3865	3935	Lime & shale
2130	2140	Sand	3935	4025	Chert & lime
2140	2530	Broken lime	4025	4088	Shale & lime
2530	2825	Shale & shells	4088	4118	Lime
2825	2835	Broken lime	4118		Total depth from ground level.

Elevation 1912'

Run 440' of 10-3/4"OD 28# Armco Spiral Weld casing; set at 437'; cemented with 400 sacks of cement.

Top of Kansas City Lime 3545'

Top of Viola Lime 3887'


Top of Arbuckle Lime 4081'

Cored from 4086' to 4096' - recovering 5' of Arbuckle Lime, no saturation, slight odor of sulphur.

Cored from 4096' to 4116' - recovering 3' of Arbuckle Lime, no show of oil, but strong odor of sulphur.

Plugged and abandoned December 18, 1941.

Total Depth 4116'



Note: All of above footages are calculated from the ground level.

FLD-JL 1/22/42
 LPC (3) File (1)

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

7 L. D.
 Name and title of representative of company

Subscribed and sworn to before me this the 22nd day of January, 1942.

My Commission expires October 21, 1944 Louis M. Laine
 Notary Public