


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 2 Twp. 24 Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Leben Drilling, Inc.
Lease Name Curtis Well No. 1
Office Address 905 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 24 1956
Application for plugging filed June 24 1956
Application for plugging approved June 24 1956
Plugging commenced June 24 1956
Plugging completed June 24 1956
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege, Hoisington, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4210 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	201'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rotary mud with 1/2 sack hulls to 210' - Plug with 25 sacks cement poured through drill pipe. Mud with 1/2 sack hulls to 35' and plug with 10 sacks cement to surface.

RECEIVED
STATE GOV
6-28-56

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James M. Battin (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Battin
905 Central Building, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of June, 19 56

My commission expires July 10, 1957

John Thomas
Notary Public.

PLUGGING
FILE SEC. 2 T. 24 R. 14W
BOOK PAGE 74 LINE 3

CONTRACTOR'S WELL LOG

COMPANY: Leben Drilling, Inc. and Russell Cobb, Jr.
 CONTRACTOR: Leben Drilling, Inc.
 FARM: Curtis #1
 LOCATION: SW SW NE, Section 2-24-14W, Stafford County, Kansas
 COMMENCED: June 10, 1956
 COMPLETED: June 24, 1956

0	35	Surface Clay
35	179	Sand
179	200	Blue Shale
200	295	Shale and Shells
295	380	Sand
380	620	Shale and Shells
620	860	Shale
860	885	Anhydrite
885	955	Shale and Lime
955	1511	Shale and Shells
1511	1815	Shale and Lime
1815	1926	Lime
1926	2016	Shale and Lime
2016	2122	Lime
2122	2245	Lime
2245	2380	Lime and Shale
2380	2485	Lime and Shale
2485	2607	Lime and Shale
2607	2817	Lime and Shale
2817	2980	Shale and Lime
2980	3110	Shale and Lime
3110	3240	Lime and Shale
3240	3350	Lime and Shale
3350	3410	Lime and Shale
3410	3455	Shale and Lime
3455	3527	Lime and Shale
3527	3630	Shale and Lime
3630	3660	Shale and Lime
3660	3702	Lime
3702	3716	Lime
3716	3760	Lime
3760	3805	Lime
3805	3824	Lime
3824	3873	Lime
3873	4075	Lime
4075	4106	Lime
4106	4123	Chirt and Lime
4123	4160	Shale and Lime
4160	4196	Lime
4196	4210	Lime
	4210	Rotary Total Depth D & A

REC
STATE CORPORATION
JUN 28 1956

Set 8 5/8" surface casing at 201' with 175 sacks of cement.

I, James M. Battin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Curtis No. 1, SW SW NE, Section 2-24-14W, Stafford County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

By James M. Battin

State of Kansas) ss:
Sedgwick County)

Subscribed and Sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 26th day of June, 1956.

John Thomas
(Notary Public)

My commission expires July 10, 1957.

PLUGGING
FILE SEC 2 T 24-14W
BOOK PAGE 74 LINE 3