


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 2 Twp. 24 Rge. 14 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NE NE SW

Lease Owner L. D. Davis
Lease Name OWEN Well No. 1
Office Address R. R. 1 Box 183 B Great Bend, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) 67530
dry hole



Locate well correctly on above
Section Plat

Date Well completed April 2 1982
Application for plugging filed April 2 1982
Application for plugging approved April 2 1982
Plugging commenced 2:00 P. M. April 2 1982
Plugging completed 3:00 P. M. April 2 1982
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Metz
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4207'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

600' W/60 sx. 50/50 Pozmix, 2% Gel, 3% CC
210' W/40 sx. " " " " " "
40' W/10 sx. " " " " " "
10 sx in rat hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. D. Drilling, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Don Popp (employee of owner) or (~~owner~~)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Popp
Don Popp Holsington, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of April, 19 82

Bessie M. DeWerff
Bessie M. DeWerff Notary Public.

My commission expires 5-20-85

RECEIVED
STATE CORPORATION COMMISSION
APR 20 1982
4-20-82

NOTARY PUBLIC - State of Kansas
BESSIE M. DeWERFF
My Appt. Exp. May 20, 1985

DRILLERS WELL LOG

L. D. DRILLING, INC. - Contractor

L. D. DAVIS - Operator

OWEN #1
NE NE SW
SEC. 2-24-14
Stafford County, Kansas

T. D. 4207'
Elevation 1956' K.B.

Commenced: 3-23-82
Completed: 4-01-82

CASING:

8 5/8 Set at 214'

CEMENT:

W/ 175 SX 50/50 Poz 2% Gel, 3% CC

FORMATION:

Sand
Red Bed
Anhy
Shale
Lime & Shale

DEPTH:

0- 214
214- 860
860- 881
881-1650
1650-4207

FORMATION TOPS:

Anhy 860- 881
Heeb 3473
Tor. 3495
Douglas 3524
Brn Lime 3612
Lans 3636
Base K/C 3885
Cong. Ch. 3973
Miss. 4038
Viola 4065
Simp 4129
Arb 4178
RTD 4207

RECEIVED
STATE CORPORATION COMMISSION

APR 20 1982

AFFIDAVIT

STATE OF KANSAS)
) SS:
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

L. D. DRILLING, INC.

Don Pop

DON POPP

Sworn to and subscribed before me this 19th day of April, 1982.

Bessie M. DeWerff

BESSIE M. DeWERFF

My Appointment Expires: 5-20-85

