

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County, Sec. 7 Twp. 24S Rge. (E) 14(W)

Location as "NE/CNW/SE" or footage from lines SE NW SE
Lease Owner Natural Gas and Oil Corporation
Lease Name Suiter Well No. 1
Office Address 1009 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed January 6, 1954 19
Application for plugging filed January 6, 1954 (Orally) 19
Application for plugging approved January 7, 1954 (written) 19
Plugging commenced January 6, 1954 19
Plugging completed January 6, 1954 19
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface		0	207	8 5/8"	207	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 4265 to 200 feet
Set plug at 200 feet and ran 20 sacks cement to 140 feet
Filled with heavy mud from 140 to 40 feet
Set plug at 40 feet and ran 10 sacks cement to cellar

RECEIVED
STATE OF KANSAS
1-14-54
JAN 14 1954

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Drilling Department of Natural Gas and Oil Corporation
Address 1009 Central Building, Wichita 2, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Harold A. Burt, Regional Manager (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold A. Burt
1009 Central Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January 1954

Esther Russell

My commission expires May 25, 1957.

Notary Public.

PLUGGING
FILE SEC 2 T24 R14W
BOOK PAGE 6 LINE 2

DRILLER'S LOG

COMPANY: Natural Gas and Oil Corporation
and
Oklahoma Exploration Company

CONTRACTOR: Drilling Department of
Natural Gas and Oil Corporation


FARM: Suiter No. 1, SE NW SE Sec 7-24S-14W
Stafford County, Kansas

COMMENCED: December 20, 1953

COMPLETED: January 6, 1954

ELEVATION: 1989 RB

0	to	9	Cellar
9	to	110	Sand
110	to	160	Blue shale
160	to	385	Shale and shells
385	to	465	Sand
465	to	934	Red bed and shells
934	to	954	Anhydrite
954	to	1760	Shale and shells
1760	to	1980	Lime and shale
1980	to	2080	Lime
2080	to	2365	Lime and shale
2365	to	2405	Lime
2405	to	2975	Lime and shale
2975	to	3050	Lime
3050	to	3070	Shale
3070	to	3330	Lime and shale
3330	to	3345	Lime
3345	to	3370	Shale
3370	to	3395	Sandy lime
3395	to	3409	Lime
3409	to	3510	Lime and shale
3510	to	3522	Shale
3522	to	3600	Lime
3600	to	3689	Shale
3689	to	3915	Lime
3915	to	3925	Shale
3925	to	3980	Shale and lime
3980	to	3996	Conglomerate
3996	to	4050	Shale and lime
4050	to	4083	Shale, lime w/chert
4083	to	4104	Chert, lime and sand
4105	to	4106	Chert
4106	to	4191	Shale, lime and chert
4191	to	4221	Shale and chert
4221	to	4235	Simpson
4235	to	4265	Arbuckle lime
		4265	T. D. RB



ED
JAN 14 1954
ELEVATION DIVISION
Wichita, Kansas

Set 207 feet of 8 5/8" 25# surface pipe. Cemented with 200 sacks cement and 4 sacks calcium chloride

TOPS:	Anhydrite	934	Lansing	3684	Viola	4116
	Heebner	3532	Base K C	3932	Simpson	4188
	Brown Lime	3673	Conglomerate	4037	Arbuckle	4235

DRILLSTEM TEST: 4079-4104, open 1 hour, shut in 15 min, gas to surface in 35 min, rec. 40' mud, 1320# BHP.

Schlumberger run

DRY, PLUGGED AND ABANDONED

PLUGGING
FILE SEC 7 T 24 R 14W
BOOK PAGE 6 LINE 17

C E R T I F I C A T E

I, Harold A. Burt, do hereby certify that the above and foregoing is a true and correct copy of the log of the Suiter No. 1, SE NW SE Section 7-24S-14W, Stafford County, Kansas, as reflected by files of the Natural Gas & Oil Corporation.

Harold A. Burt
Harold A. Burt, Regional Manager

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 12th day of January, 1954.

Esther Unsell
Esther Unsell, Notary Public

My commission expires May 25, 1957.

NOTARY PUBLIC
Sedgwick County, Kansas