


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 20 Twp. 29 Rge. 14 (E) 14 (W)  
Location as "NE/CNW/SW" or footage from lines SW SW SW  
Lease Owner Musgrove Petroleum Corporation  
Lease Name SCHPEPEL Well No. 1  
Office Address 518 Petroleum Bldg., Wichita, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed December 22, 1954  
Application for plugging filed verbally - December 21, 1954  
Application for plugging approved verbally - December 21, 1954  
Plugging commenced December 22, 1954  
Plugging completed December 22, 1954  
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? verbally - yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 4765 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	315'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 300'  
Set 1st plug at 300' with 20 sacks cement  
Filled hole with mud to 35'  
Set 2nd plug at 35' with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Musgrove Petroleum Corporation  
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF KANSAS, COUNTY OF Sedgwick  
Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling  
518 Petroleum Building, Wichita, Kansas.  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of December, 1954  
Notary Public.

My commission expires September 24, 1956.

PLUGGING  
FILE SEC 20, 29 R 14W  
BOOK PAGE 87 LINE 19

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 3 - 1955  
01-03-55  
CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	SCHREPPEL #1
LOCATION:	SW SW SW, Sec. 20-29-14, Pratt County, Kansas.
COMMENCED:	December 8, 1954
COMPLETED:	December 22, 1954

0	75	Surface soil & clay
75	225	Sand
225	855	Red bed
855	865	Red bed & shale
865	900	Anhydrite
900	2015	Shale & shells
2015	2175	Anhydrite & lime
2175	4027	Lime & shale
4027	4061	Lime, sand & shale
4061	4142	Lansing
4142	4467	Lime
4467	4525	Lime & shale
4525	4539	Chert & lime
4539	4607	Chert, lime & shale
4607	4664	Chert & lime
4664	4720	Chert, lime, sand & shale
4720	4735	Sand, lime & shale
4735	4765	Arbuckle lime
	4765	Rotary Total Depth

Set 8-5/8" surface casing at 315' with 265 sacks of cement & 4 calcium chloride.  
Dry and Abandoned.

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the SCHREPPEL #1, SW SW SW, Section 20-29-14, Pratt County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY *Gordon L. Koelling*  
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 29th day of December 1954.

*Alma H. Stenning*  
Notary Public

My commission expires September 24, 1956.

PLUGGING  
ALL SEC 20-29-14W  
BOOK PAGE 4765-4

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 3 - 1955  
CONSERVATION DIVISION  
Wichita, Kansas