


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Pratt County. Sec. 16 Twp. 29 Rge. (E) 14 (W)  
Location as "NE/CNW/SW" or footage from lines NW NW SE  
Lease Owner Lario Oil & Gas Company  
Lease Name Schrepel Well No. 1  
Office Address 301 South Market, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 21 19 54  
Application for plugging filed (Verbal) August 21 19 54  
Application for plugging approved August 21 19 54  
Plugging commenced August 21 19 54  
Plugging completed August 21 19 54  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation Depth to top Bottom Total Depth of Well 4715 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Red bed		0	358	8 5/8"	358'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4715' back to 300' heavy rotary mud with plug and 20 sacks cement.  
300 back to 40' heavy rotary mud with top plug and 10 sacks cement placed through drill pipe. Top plug wired.

REC'D  
STATE CORPORATION COMMISSION  
AUG 28 1954 08-28-54  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Buick Drilling Inc.  
Address P.O. Box 331, St. John, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Leo Ross (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Leo Ross*  
301 South Market, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of August, 19 54

My commission expires July 21, 1958 *Frances Bealie* Notary Public.

PLUGGING  
FILE SEC 16 TWP 29 R 14W  
BOOK PAGE 58 LINE 10

LARIO OIL & GAS COMPANY  
 No. 1 Schrepel  
 NW NW SE Sec. 16-29-14W  
 Pratt County, Kansas

Drilling Commenced: 7-28-54  
 Drilling Completed: 8-21-54  
 Drilling Contractor: Buick Drilling, Inc.  
 Total Depth 4715'  
 I.P. - Dry and Abandoned

Casing Record:  
 8 5/8" 364'6" set at 358'  
 Cem. 270 sacks

Formation	Depth
Clay & soil	35
Sand	145
Sand & gravel	210
Red bed & shale	358
Red bed & shells	855
Anhydrite	875
Red bed & shale	1300
Shale & shells	1420
Salt and shale	1550
Shale & shells	1770
Shale & lime	2385
Lime	2475
Lime & shale	3415
Lime	3475
Lime & shale	3593
Lime	3635
Lime & shale	3725
Lime	3770
Lime & shale	3975
Sand, lime & shale	4028
Lime	4065
Lime & shale	4120
Lime	4152
Lime & shale	4180
Lime	4210
Lime & shale	4280
Lime	4310
Lime & shale	4360
Lime	4390
Shale & lime	4550
Chert, lime & shale	4611
Chert, lime, shale & sand	4635
Lime & shale	4680
Lime	4701
Lime & shale	4715

Geological Tops:		
Elev.	2015 D.F.	2018 R.B.
Topeka	3224	-1206
Heebner	3842	-1824
Base Oread	3892	-1874
Douglas Sd	3978	-1960
Lansing	4033	-2015
Marmaton	4367	-2349
Conglomerate	4484	-2466
Viola	4548	-2530
Simpson Sh.	4592	-2574
Sp. Dolomite	4598	-2580
Simpson Sd.	4625	-2607
Arbuckle	4693	-2675
Rotary T.D.	4715	-2697
Schlumberger		
T.D.	4716	-2698

\*\*\*\*\*

I hereby certify that this is a true and correct log of the above mentioned well.

*Leo Ross*

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Subscribed and sworn to before me, a notary public, in and for said County and State this 26th day of August, 1954.

*Frances Lealie*  
 Notary Public

My Commission expires July 21, 1958.

**PLUGGING**  
 FILE SEC. 16-29-R-14W  
 BOOK PAGE 58 LINE 10

NOTARY PUBLIC  
 STATE OF KANSAS  
 My Commission Expires July 21, 1958  
 NOTARY PUBLIC  
 STATE OF KANSAS