


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 15 Twp. 29 Rge. 14 (E) W. (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines 330' N. & 330' W. of S/4 Cor.
Lease Owner Cities Service Oil Company
Lease Name Luther "D" Well No. 1
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 11, 19 53
Application for plugging filed February 11, 19 53
Application for plugging approved February 11, 19 53
Plugging commenced February 11, 19 53
Plugging completed February 11, 19 53
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 4732 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	409'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4732-300', mud.
300-250', wood plug and hulls, and 20 sacks cement.
250- 35', mud.
35' to base of cellar, wood plug and 10 sacks cement.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lohmann-Johnson Drilling Co., Inc.
Address Evansville, Indiana

STATE OF Kansas, COUNTY OF Barton, ss.
V. M. Conover (employee of owner) or ~~owner or operator~~ of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *V. M. Conover*

Box 751, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of February, 19 53

W. G. Smith
Notary Public.

My commission expires March 12, 1955.

PLUGGING
FILE SEC 15 T 29 R 14
BOOK PAGE 78 LINE 37

WELL RECORD

Company Cities Service Oil Co. Well No. 1 Farm Luther "D"
 Location 330' North and 330' West of S/4 Cor. Sec. 15 T. 29 R. 14W
 Elevation 1988 (1986 Gr.) County Pratt State Kansas
 Drlg. Comm. January 14, 1953 Contractor Lohmann-Johnson Drlg. Co., Inc.
 Drlg. Comp. February 10, 1953 Acid None
 T. D. 4732' Initial Prod. Dry Hole; P. & A. 2-11-53.

CASING RECORD:

10-3/4" @ 409' cas. 350 ex cement

FORMATION RECORD:

sand	0-200
red bed	415
red bed & shells	830
shale & shells	1730
shale & lime	1820
lime	2500
lime & shale	2931
shale & lime	2938
broken lime	3091
lime & shale	3200
lime	3476
broken lime	3502
lime	3891
sand	3940
lime	4321
lime & shale	4414
chert & lime	4482
chert	4560
chert & shale	4575
cherty lime	4585
sand	4598
shale & sand	4682
lime	4732 T. D.

Top Topeka	3218'
Top Douglas Sand	3890'
Top Brown Limestone	3997'
Top Lansing	4015'
Top Conglomerate	4471'
Top Mississippi	4474'
Top Viola	4516'
Top Simpson Shale	4584'
Top Simpson Sand	4590'
Top Arbuckle	4682'
Penetration	50'
Total Depth	4732'

Drill Stem Test 3960-97, open
 1 hr., recovered 105' salt water;
 B. H. P. 1260#/15 mins.

Drill Stem Test 4586-98, open
 1 hr., recovered 150' salt water;
 B. H. P. 1283#/20 mins.

SYFO:

350'	1°
1000'	1°
1500'	1°
2000'	3°
2064'	3°
2150'	1°
2250'	2°
2500'	1°
3170'	1°
3595'	2°
4272'	1°

PLUGGING

FILE SEC 15 T 29 R 14W
 BOOK PAGE 78 LINE 37

RECEIVED
 STATE COMMISSION

FEB 20 1953

CONSERVATION DIVISION
 Wichita, Kansas