

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-20,975-0000

LEASE NAME Chisholm #1-10

WELL NUMBER _____

SPOT LOCATION SE NE SE

SEC. 10 TWP. 22 SRGE. 10 (W or E) or (S or N)

COUNTY Reno

Date Well Completed _____

Plugging Commenced 4/23/84

Plugging Completed 4/25/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Sterling Drilling Co.

ADDRESS Box 129, Sterling, Ks. 67579

PHONE # (316) 278-2131 OPERATORS LICENSE NO. 5142

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filled? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3645'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	265'	none
				4 1/2"	3640'	2750'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each snt.

Pumped bottom with 40 sacks cement, pumped plug to 3156'. Shot pipe at 2765' & pulled 65 joints of pipe. Plugged well with 2 bulls, 6 gal. plug, & 100 sacks 60/40 poz 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION
MAY 02 1984

CONSERVATION DIVISION expires:
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 1st day of May, 19 84



Irene Hoover
Notary Public

Form CP-4
Revised 6-83

15-155-209750000

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - CHISHOLM #1

Located: SE NE SE, Section 10-22S-10W, Reno County,
Kansas

OWNER: Lebsack Oil Production

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 13, 1984

COMPLETED: February 20, 1984

TOTAL DEPTH: 3645'

LOG

0 - 180 Sand

180 - 1053 Shale

1053 - 3645 Lime and Shale

CASING RECORD

Ran 6 joints new 8 5/8", 23# casing.
252.02' pipe set at 265' K.B. Cemented
with 250 sacks 60/40 Pozmix, 2% gel,
3% cc. Plug down at 4:30 PM, 2-13-84,
by Halliburton.

Ran 87 joints 4 1/2" used 9.5# casing.
3630.65' pipe set at 3640' K.B. Cemented
with 50 sacks Lite and 125 sacks Regular
Pozmix, 2% gel, salt saturated. Plug
down at 3:30 AM, 2-20-84, by Halliburton.

Deviation Surveys: 1° at 1732'
2° at 3393'
2° at 3645'

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1984

CONSERVATION DIVISION
Wichita, Kansas