


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Reno County, Sec. 12, Twp. 22, Rge. 10 (E) W(W)  
Location as "NE/CNW/SW" or footage from lines. SE SE NW  
Lease Owner E. H. Riggs  
Lease Name Brown Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 6-9-64 19  
Plugging completed 6-11-64 19  
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3227 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	212'	None
				5-1/2"	3217'	2565'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3227', pushed plug to 3110' and ran sand to 3100'. Dumped 5 sacks of cement @ 3100' with dump hauler. Pulled 5 1/2" casing, bailed fluid to 210', set rock bridge to 200' and dumped 20 sacks of cement @ 200'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

6-17-64  
RECEIVED  
STATE CORPORATION COMMISSION

JUN 17 1964

PLUGGING COMPLETE.

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of June, 1964

My commission expires May 20, 1968

Milton J. Volin  
Notary Public.

15-155-00428-0000

ELEVATION: 1742' RB  
1739' DF  
1737' OL

BROWN #1

REX & MORRIS DRILLING COMPANY AND E. H. RIGGS

TOTAL DEPTH 3627' RB  
CONTRACTOR REX & MORRIS DRILLING CO  
COMMENCED 5-14-63  
COMPLETED 5-29-63  
INITIAL PRODUCTION 25 BOPD

LOCATION: SE SE NW  
SECTION 12-22S-10W  
RENO COUNTY, KANSAS

CASING RECORD:  
8 5/8" @ 212' W/200 SACKS  
5 1/2" A 3217' W/100 SACKS


<u>FORMATION</u>	<u>DEPTH</u>
SURFACE HOLE	212
SHALE	1265
LIME AND SHALE	2040
SHALE AND LIME	2325
LIME AND SHALE	2660
LIME	2805
LIME AND SHALE	2995
SHALE AND LIME	3088
LIME	3382
LIME AND SHALE	3470
LIME	3521
SHALE AND LIME	3596
LIME	TD 3627

5-25-64

R.U.S.T., C.O. TO 3172. BAN GAMMA RAY LOG. PERFORATE  
3138'-3142', FOUR SHOTS PER FOOT, ACID 2000 GAL, TEST.  
P.B. 3130', PERFORATE 3122'-3126', ACID 2000 GAL, TEST.  
DRILL OUT PLUG AND P.O.P.

I HEREBY CERTIFY THE FOREGOING STATEMENTS ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REX & MORRIS DRILLING COMPANY

BY   
PAUL D. KOONITZ, GEOLOGIST

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BUTLER)

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC, THIS 31ST DAY OF MAY, 1963.

  
J. L. JAUER - NOTARY PUBLIC

MY COMMISSION EXPIRES: 17 JANUARY 1964