


15-155-02047-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Renosn _____ County. Sec. 21 Twp. 22S Rge. 10 (E) W (W)
Location as "NE/CNW/SW" or footage from lines Center SE SW SW
Lease Owner Phillips Petroleum Company
Lease Name Schweizer Well No. 1
Office Address Box 779, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed June 14, 1954
Application for plugging filed June 14, 1954
Application for plugging approved June 16, 1954
Plugging commenced June 16, 1954
Plugging completed June 24, 1954
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruell Durkee
Producing formation Arbuckle Depth to top 3656' Bottom 3676' Total Depth of Well FB 3595' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	Dry	3020		10-3/4"	313'	
Toronto	Dry	3040				
Lansing Kansas City	Dry	3192				
Marmaton	Dry	3484				
Viola	Dry	3558				
Simpson	Dry	3588				
Simpson Sand	Dry	3608				
Arbuckle	Dry	3656				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole from FBTD 3595' to 275'. Dumped 20 sx cement 275' to 220'. Mudded to 10' and dumped 5 sx cement in filling to base of cellar. Well plugged and abandoned at 6:00 PM. 6-24-54

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
A. J. Willis, District Superintendent (employee of owner) ~~and owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 779, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of June, 1954

My commission expires November 18, 1957
Joseph M. Neal Notary Public.

PLUGGING
FILE SEC 21 22 10W
BOOK PAGE 41 LINE 21

6-29-54

EXPLORATION RECORD

Lease Switzer

Well 2

Formation Name	Top	Base	Remarks
			Elevation: 1775 D. F.
Sand, shale & shells	0	341	
Shale, salt & shells	341	1248	
Shale & lime	1248	1595	
Lime	1595	1792	
Lime & shale	1792	1920	
Shale	1920	2267	
Shale & lime streaks	2267	2402	
Lime & shale	2402	2491	
Shale	2491	2605	
Shale, lime & sand	2605	2762	
Lime	2762	2895	
Lime & shale	2895	3241	
Lime	3241	3565	
Chert, shale & lime	3565	3604	
Shale	3604	3621	
Sand & shale	3621	3653	
Lime	3653	**3676	
			Top:
			Tortic 2392
			Elment 2461
			Happy Hollow 2514
			Howard 2640
			1st Severy sand 2678
			2nd Severy sand 2692
			Topeka 2728
			Boehmer 3020
			Toronto 3040
			Dr. Limestone 3162
			INC 3192
			Base INC 3475
			Marraton 3484
			Viola 3558
			Simpson 3589
			Simpson sand 3608
			Artuckle 3656
			** Not penetrated at TD 3676'. Plugged back to producing formation 3595'.

PLUGGING
 FILE SEC 21 T 22 R 10W
 BOOK PAGE 41 LINE 21

10-29-54

REC
STATE CORP

CONSE
WILL

- 1 - Evils
- 1 - F. W. Shelton
- Form 881.3-53 Film
- 1 - Geo. Evils Div Ofc
- 1 - Geo. District Ofc