


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Reno County, Sec. 21 Twp. 22 Rge. 10 (E) W. (W)
Location as "NE/CNW/SW" or footage from lines. NE NE NE
Lease Owner Cities Service Oil Company
Lease Name Schweizer Well No. 1
Office Address Box 144, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed April 4, 1952
Application for plugging filed April 1, 1957
Application for plugging approved April 2, 1957
Plugging commenced May 11, 1957
Plugging completed May 21, 1957
Reason for abandonment of well or producing formation Depleted formation.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production April 24, 1957
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Lansing Depth to top 3155 Bottom 3526 Total Depth of Well 3546 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	326'	None
				5-1/2"	3528'	1870'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3351-3175', river sand.
3175-3127', 6 sacks cement.
3127- 250', heavy mud.
250- 190', rock bridge and 15 sacks cement.
190- 25', heavy mud.
25' to base of cellar, rock bridge and 5 sacks cement.

5-23-57

RECEIVED
STATE CORPORATION COMMISSION

MAY 23 1957

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C. E. Schull Casing Pulling Company
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. M. Conover (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. M. Conover
Box 144, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 19 57

W. B. Smith
Notary Public.

My commission expires March 12, 1959.

PLUGGING
IF SEC 21 T 22 10 W
BOOK PAGE 3 LI 33

WELL RECORD 15-155-03151-0000

Company Cities Service Oil Co. Well No. 1 Farm Schweizer
 Location 330' South and 330' West of NE Corner Sec. 21 T. 22 R. 10W
 Elevation 1760 (1758 Cr.) County Rego State Kansas
 Drlg. Comm. March 13, 1952 Contractor Hola Drilling Company
 Drlg. Comp. April 4, 1952 Acid 8500 gals. (see below)
 T.D. 3546' Initial Prod. Physical Potential: 234 oil, 38 water, 24 hrs. (6-2-52)
 P.B.T.D. 3351'

CASING RECORD:

8-5/8" O 326' cen. 225 ex cement
 5-1/2" B 3528' cen. 125 ex cement

FORMATION RECORD:

sand & clay	0-200
red bed	327
red bed & shale	500
anhydrite	550
shale & shells	1410
lime & shale	1730
lime	1850
lime & shale	1975
shale	2490
shale & lime	2550
lime & shale	2720
lime	2780
lime & shale	3020
shale & lime	3145
lime	3270
lime & shale	3325
lime & chert	3347
lime	3430
lime, shale & chert	3474
lime & chert	3529
3529 STD = 3528 SLH	
lime & chert	3546 T. D.

Corr. Brown Limestone	3131'
Corr. Lansing	3155'
Corr. Viola	3528'
Penetration	20'
Total Depth	3546'

5 gals. water per hr. with trace oil at 3536.

4-2-52 Az. 500 gals. at T. D. 3536; subd. 12 gals. wtr./hr.

Deepened 3536-46, total depth.

Set Baker plug at 3552; 1 gal. rock on plug; P. B. T. D. 3351 S. L. H.

Perf. 61 shots 3203-20.

4-6-52 Az. 1000 gals. 3203-20.

Perf. 23 shots 3184-90.

4-7-52 Az. 1000 gals. 3184-90.

4-10-52 Fmrd. 32 oil, 15 wtr., 24 hrs. from zones 3184-90 and 3203-20.

4-11-52 Az. 3000 gals. 3184-90.

4-14-52 Az. 3000 gals. 3203-20.

SYFO: 500' 1°
 1000' 1°
 1500' 1°
 2000' 1°
 2500' 0°
 3000' 1°
 3500' 1°

D. S. T. 3184-3191, open 1 hr., recovered 20' heavily oil and gas-cut mud and 60' slightly oil and gas-cut mud; B. H. P. 620#/15 mins.

4-2-57

RECEIVED
 STATE CORPORATION COMMISSION

APR 2 - 1957

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING

FIL. SEC. 21 T. 22 R. 10W
 BOOK PAGE 3 LINE 33