

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Reno

County. Sec. 22 Twp. 22S Rge. 10W (E) (W)

T 22S NORTH R 10W

*			
	22		

Locate well correctly on above Section Plat

Location as "NE/CNW\*SW\*" or footage from lines. NW NW NW  
Lease Owner Lawrence Supply Co., Inc.  
Lease Name H. F. Sankey Well No. 1  
Office Address Box 448 - Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed July 11 1951  
Application for plugging filed October 9 1956  
Application for plugging approved October 10 1956  
Plugging commenced November 7 1956  
Plugging completed November 12 1956  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production August 1956  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3679 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8"	254'	None
				7" OD	3659'	2351'
				Hole plugged back to 3461' and casing perforated from 3187' to 3195'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled the hole with sand from 3461' to 3150' and ran 6 sacks of cement. Mudded the hole to 245', set a 10' rock bridge and ran 20 sacks of cement. Mudded the hole to 35', set a 10' rock bridge and ran 10 sacks of cement to base of cellar. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.  
Noel J. Bright (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Noel J. Bright  
Chase, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 14th day of November 1956  
Edward E. Brown Notary Public.

My commission expires May 20, 1957

PLUGGING  
FILE SEC. 22 T. 22 R. 10W  
BOOK PAGE 106 LINE 53

NOV 15 1956  
11-15-56  
CONSERVATION DIVISION  
Wichita, Kansas

15-155-00368-0000


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock Wichita, Kansas

Company - THE ATLANTIC REFINING CO.  
Farm - H. F. Sankey No. 1

SEC. 22 T. 22 R. 10W  
NW NW NW

Total Depth. ~~3689~~ PB 3461  
Comm. 5-22-51 Comp. 7-11-51  
Shot or Treated.  
Contractor.  
Issued. 9-8-51

County. Reno KANSAS



CASING:  
9 5/8" 254' cem w/250 sx.  
7" 3659' cem.

Elevation. 1761 DE  
Potential  
Production. 505 BOPD & 15% wtr.

Figures Indicate Bottom of Formations.

surface sand & clay	40
sand	120
shale	215
red bed	510
red bed, shale & shells	823
shale & shells	1600
sandy lime	1690
lime	1925
sandy lime	1995
lime & shale	2685
shale & shells	2700
lime	2755
lime & shale	2800
lime	2980
shale & lime	3192
lime	3240
lime & shale	3300
lime	3335
lime & shale	3375
lime	3396
lime & shale	3399
lime	3470
lime & shale	3533
lime, shale & chert	3582
shale	3615
shale & sand	3669
Total Depth: PBD 3461	3612
Comm. Depth: PB 3461	
Tops: Lane-Well	
Hebnergs:	2994
Brown Lime	3134
Lansing	3160
Viola	3527
Simpson Sand	3581
Arbuckle	3635

Producing in Area: 3187 - 3195  
(K.C. lime)

PLUGGING  
FILE SEC. 22 T. 22 R. 10W  
BOOK PAGE 106 LINE 53

11-13-56  
RECEIVED  
CORPORATION COMMISSION  
NOV 13 1956  
CONSERVATION DIVISION  
Wichita, Kansas