

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-19503-00-01

API NUMBER _____

LEASE NAME Ruder "D"

WELL NUMBER 1-A

1650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 8 TWP. 15 RGE. 18 ~~XX~~ or (W)

COUNTY Ellis

Date Well Completed 6-1961

Plugging Commenced 6-9-92

Plugging Completed 6-9-92

LEASE OPERATOR Diehl Oil, Inc.

ADDRESS P. O. Box 234 Hays, KS 67601
PHONE# (913) 625-6711 OPERATORS LICENSE NO. 09346
Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-8-92 (date)

by Don Butcher, witnessed by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

disposing Arbuckle Formation Depth to Top 3588 Bottom 3765 T.D. 3827

XXXXXX

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	146'	-0-
				5 1/2"	3738'	-0-
		DV tool @ 1160' cemented with 400 sacks (cement circulated)				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Tubing parted @ 958'. Recovered tubing to a depth of 1197'. Ran in tubing to 1130'. Pump 200 sacks class A, 200 sacks 65/35 poz 8% gel 2 sacks hulls, 150 sacks 65/35 poz 8% gel 2 sacks hulls max psi 500#. Unable to pull out tubing. Backed off tubing. Lost 16 joints in hole. Squeeze with 50 sacks 65/35 poz max 100# 50# shut in. If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BJ Services License No. _____


Address 1707 East 10th Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Diehl Oil, Inc. P. O. Box 234 Hays, KS

STATE OF Kansas COUNTY OF Ellis, ss.

Glenn D. Diehl

(XXXXXX or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Glenn D. Diehl

(Address) P. O. Box 234 Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 16th day of June, 1992

My Commission Expires: 02/05/94

Rebecca Diehl
Notary Public

JUN 22 1992

6-22-92
CONSERVATION DIVISION

Wichita, Kansas CP-4
Revised 05-88