

STATE OF KANSAS
STATE CORPORATION COMMISSION
115 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-185-10977-00-00 ~~22726~~

API NUMBER 15-185-20,726

LEASE NAME O'Connor

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from S Section Line

2310
3630 Ft. from E Section Line

SEC. 8 TWP. 24S RGE. 12W (E) or (W)

COUNTY Stafford

LEASE OPERATOR Rama Operating Co., Inc.

ADDRESS P.O. Box 159 Stafford, Kansas 67578

PHONE# (316) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

Date Well Completed _____

Plugging Commenced 2-8-00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-9-00

Is plugging proposal was approved on _____ (date)

By Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3874'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				3-5/8"	205'	None
				5-1/2"	3870'	1910'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from _____ feet to _____ feet each section. Plugged off bottom with sand to 3800' and 5 sks. cement. Shot pipe @2500', 2210' and 1910'. Pulled up to 710', pumped 10 sks. gel, 50 sks. cement, pulled up up to 230', pumped 40 sks. cement, pulled casing out and topped off with 15 sks. cement. 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rama Operating Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED
STATE CORPORATION COMMISSION
2-18-2000
FEB 18 2000

SUBSCRIBED AND SWORN TO before me this 17th day of February 2000

[Signature]
Notary Public

CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires: _____



Form 6
Revised 05-