


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 8 Twp. 24S Rge. 12 (W)
Location as "NE/CNW%SW%" or footage from lines A/C S/2 NW/4 SW/4
Lease Owner Barnett Oil Company
Lease Name Parks Well No. 2
Office Address 411 First Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 25, 1962
Application for plugging filed March 26, 1962
Application for plugging approved March 26, 1962
Plugging commenced March 25, 1962
Plugging completed March 25, 1962
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation Depth to top Bottom Total Depth of Well 3880 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
-	Water	30'	40'	8 5/8"	214'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Circulated heavy mud to bottom of hole. Set plug at 200' with 1/2 sack of hulls on top and 25 sacks of cement. Filled hole with heavy mud to 35'. Set plug at 35' with 1/2 sack of hulls on top and cemented to bottom of cellar with 10 sacks of cement.

Plugged rat hole with 1 sack of hulls to bridge and 3 sacks of cement.

Plugging completed at 4:30 P.M., 3/25/62.

(Well Log attached)

RECEIVED
STATE CORPORATION COMMISSION
4-5-62
APR 5 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnett Drilling, Inc.
Address 409 First National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
F. H. Rousey (employee of Barnett Drilling, Inc. or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. H. Rousey
411 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of April, 1962

My commission expires February 27, 1964. Mildred F. Willis Notary Public.



BARNETT OIL COMPANY
WELL LOG - PARKS NO. 2
A/C S/2 NW/4 SW/4 SECTION 8-24S-12W
STAFFORD COUNTY, KANSAS

<u>From</u>	<u>To</u>	<u>Formation</u>
0	30	Shale
30	40	Sand
40	214	Shale and shells
214	697	Shale and Red Bed
697	720	Anhydrite
720	1740	Shale and shells
1740	3110	Lime and shale
3110	3195	Chalk, lime and shale
3195	3645	Lime and shale
3645	3805	Lime
3805	3870	Lime and shale
3870	3880	Lime chert (T.D.) (D. & A.)

Set 214' of 8 5/8", 28# casing with
200 sacks of cement.

RECEIVED
STATE CONSERVATION COMMISSION
APR 5 1962
CONSERVATION DIVISION
Wichita, Kansas