

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Reno County, Sec. 21 Twp. 22S Rge. 10 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE

Lease Owner National Cooperative Refinery Association

Lease Name Schweizer Well No. 1

Office Address Third Floor Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed January 6, 19 54

Application for plugging filed November 18, 19 53

Application for plugging approved November 19, 19 53

Plugging commenced January 5, 19 54

Plugging completed January 6, 19 54

Reason for abandonment of well or producing formation Depletion of producing formation.

If a producing well is abandoned, date of last production October 30, 19 53

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruell Durkee

Producing formation Viola Depth to top 3541 Bottom 3583 Total Depth of Well 3593 Feet

Show depth and thickness of all water, oil and gas formations. PB TD - 3593'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	280'	Cemented
				5 1/2"	3633'	2799'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded hole from 3593' to 3535', dumped 6 sacks of cement to 3485'. Mudded hole to 200', set 10' rack bridge, dumped 15 sacks cement to 150', mudded hole to top, ran 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. R. Sears (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears

(Address)

SUBSCRIBED AND SWORN TO before me this 12 day of January, 19 54

My commission expires June 30, 1954

G. Orville May Notary Public.

PLUGGING  
FILE SEC 21 T 22 R 10A  
BOOK PAGE 143 LINE 33

G. Orville May  
1-13-54

#1 Schweizer  
Location: 21-22-10W Reno County, Kansas  
Contractor: J. W. Braden Drilling Company  
Company: National Cooperative Refinery Association  
Date Started: 11-29-51  
Date Completed: 12-18-51

Surface	0 to 140
Sand	140 to 235
Red Rock	235 to 281
Shale	281 to 1000
Shale and Lime Shells	1000 to 1175
Shale and Shells	1175 to 1370
Lime	1370 to 1540
Lime and Shale Broken	1540 to 1640
Lime and Shale	1640 to 2045
Shale and Shells	2045 to 2265
Shale and Lime	2265 to 2445
Lime	2445 to 3125
Lime and Shale Broken	3125 to 3190
Lime	3190 to 3555
Lime and Chert	3555 to 3575
Lime	3575 to 3585
Sand	3585 to 3590
Lime	3590 to 3634 Total Depth

CASING RECORD

286' of 8-5/8" Surface Pipe  
3633' of 5-1/2" Casing Cemented with 125 sacks cement 1 foot off bottom.

STATE OF KANSAS )  
                  ) SS:  
COUNTY OF RENO )

I hereby certify that the above information is true and correct to the best of my knowledge.

J. W. Braden

Subscribed and sworn to before me this 31st day of December, 1951.

M. L. Bowman  
Notary Public

My Commission Expires:  
March 21, 1953

RECORDED  
INDEXED

NOTARY COMMISSION  
NOV 19 1953  
CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC 21 T 22 R 10W  
BOOK PAGE 143 LINE 33