

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 25 Twp. 24 Rge. 12 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SW NW SW

Lease Owner Clinton Oil Company

Lease Name Kessler Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 1-23-64 19

Plugging completed 1-29-64 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation Depth to top Bottom Total Depth of Well 4116 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	240'	None
				5-1/2"	4116'	3007'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to plug back @ 4080', sanded to 3800' and dumped 5 sacks of cement @ 3800' with dump bailer. Pulled 5 1/2" casing, checked surface, bailed fluid to 200', set rock bridge to 190' and dumped 25 sacks of cement @ 190'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

FEB 19 1964
2-19-64
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (INDEX OR REGISTER) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of February, 19 64

Milton J. Volin
Notary Public.

My commission expires May 20, 1964

DRILLERS' LOG

Company:	Clinton Oil Co. & Navajo Drilling Co.
Contractor:	Navajo Drilling Co.
Farm:	#1 Kissling, SW NW SW Sec. 25-24S-12W Stafford Co., Kansas
Commenced:	11/20/63
Completed:	11/29/63
Casing:	8-5/8" @202' w/200 sx. 5-1/2" @4118' w/150 sx.

0	-	40	Surface clay
40	-	135	Clay, sand
135	-	202	Shale & shells
202	-	364	Shale & shells
364	-	645	Red bed
645	-	670	Anhydrite
670	-	1100	Shale & shells
1100	-	1700	Shale & shells
1700	-	1920	Lime
1920	-	2100	Lime
2100	-	2325	Shale & lime
2325	-	2510	Shale & lime
2510	-	2715	Shale & lime
2715	-	2925	Shale & lime
2925	-	2980	Shale & Lime
2980	-	3080	Lime
3080	-	3180	Lime
3180	-	3299	Shale & Lime
3299	-	3410	Marmaton
3410	-	3477	Douglas
3477	-	3509	Brn. Lime
3509	-	3512	B.K.C.
3512	-	3604	Lime & shale
3604	-	3645	Lime
3645	-	3730	Lime
3730	-	3800	Lime & shale
3800	-	3836	Marmaton
3836	-	3895	Lime & shale
3895	-	3938	Shale & lime
3938	-	3945	Viola
3945	-	3963	Viola
3963	-	4010	Viola
4010	-	4032	Shale & lime
4032	-	4033	Simpson Sand
4033	-	4035	Sand
4035	-	4060	Shale
4060	-	4115	Shale & lime
		4115	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

FEB 19 1964

CONSERVATION DIVISION
Wichita, Kansas

I, George R. Jones, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Kissling, SW NW SW, Sec. 25-24S-12W, Stafford Co., Kansas, as reflected by the files of Navajo Drilling Co.

George R. Jones

GEORGE R. JONES

State of Kansas, County of Sedgwick) ss:
Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 3rd day of December, 1963.

My Commission Expires:
February 1, 1964

Barbara J. Layton

Barbara J. Layton, Notary Public