
15-185-01491-0003

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Stafford County. Sec. 29 Twp. 24S Rge. 12 (E) (W)

Location as "NE/CNW¼SW¼" or footage from lines NE NE SE

Lease Owner BRUNSON-SPINES

Lease Name BUCKLE Well No. 1

Office Address 333 First National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-21 1958

Application for plugging filed 7-21 1958

Application for plugging approved 7-21 1958

Plugging commenced 7-21 1958

Plugging completed 7-21 1958

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation Depth to top Bottom Total Depth of Well 4210 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	281½'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Circulated hole with very heavy mud. Laid down Drill pipe. Pushed plug to 240'. Covered with 1/2 sack hulls and 20 sx cement, mixed and poured through 8 jts. of Drill pipe. Hole filled within 35' of cellar bottom. Plug pushed to 35', or to fluid level, covered with 1/2 sack hulls and 15 sacks cement. All plugs secured with two strands of .066 HOWCO steel line. Mixed 5 sacks cement and plugged rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Brunson Production & Exploration, Inc.,

Address 333 First National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Ralph B. McLaughlin (employee of owner) ~~or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph B McLaughlin

Ralph B. McLaughlin
333 First National Bank Bldg., Wichita
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of July, 1958

Mary G. LaFollette
Mary G. LaFollette Notary Public.

My commission expires June 16, 1959

PLUGGING
FILE SEC 29 T 24 R 12W
BOOK PAGE 118 LINE 20

RECEIVED
STATE CORPORATION COMMISSION
7-26-58
JUL 26 1958
CONSERVATION DIVISION
Wichita, Kansas

5441

BRUNSON-SPINES
Wichita, Kansas

WELL: BUCKLE #1 — NE NE SE

COMMENCED RD: 7-9-58 — 29-24S-12W
COMPLETED RD: 7-21-58

STAFFORD COUNTY, KANSAS

TOTAL DEPTH: 4210' — ELEVATION: 1896 RB

CASING: 281½' - 8-5/8" — CONTRACTOR: BRUNSON PROD. & EXPLOR. INC.

STRATA	DEPTH	TOPS	
Surface soil & clay	10	Heebner	3370 (-1474)
Sand & Clay	50	Douglas	3407 (-1511)
Sand	170	Brown Lime	3523 (-1627)
Sand & gravel	200	Lansing	3548 (-1652)
Clay, sand & gravel	283	Base Kansas City	3790 (-1894)
Red Bed & shells	738	Viola	3972 (-2076)
Anhydrite	770	Simpson	4098 (-2202)
Shale & Shells	1235	Reworked Arbuckle	4158 (-2262)
Salt & shale	1550	Arbuckle	4167 (-2271)
Shale & Shells	1650	T. D.	4210 (-2314)
Lime	2240		
Lime & Shale	2775		
Shale - sandy	2815		
Lime & Shale	3085		
Lime	3180		
Lime & shale	3240		
Lime	3414		
Lime & Shale	3494		
Lime	3860		
Lime & Chert	3932		
Lime	3975		
Lime & Chert	4042		
Chert	4074		
Lime & Chert	4115		
Lime	4210		
Total Depth	4210		

D & A

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling report.

BRUNSON-SPINES

Ralph B. McLaughlin

Signed and sworn to in my presence this 24th day of July, 1958, by Ralph B. McLaughlin, ofcBrunson-Spines.

Mary G. LaFollette, Notary Public

My commission expires June 16, 1959.

RECEIVED
STATE CORPORATION COMMISSION
JUL 26 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 29 T 24 R 12W
BOOK PAGE 118 LINE 20