

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County. Sec. 34 Twp 24S Rge. 12 (W)

Location as "NE/CNW/SW" or footage from lines 330' S of NL, 330' E of WL, NW1/4

Lease Owner Gulf Oil Corporation

Lease Name Wanda Well No. 1

Office Address Box 661, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-29-54

Application for plugging filed 3-31-54

Application for plugging approved 3-31-54

Plugging commenced 3-31-54

Plugging completed 3-31-54

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Arbuckle Depth to top 4116 Bottom 4150 Total Depth of Well 4150 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	696'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled 4150' to 300' with heavy rotary mud, set bridge at 300' consisting of hulls and HOWCO cement plug. Spotted 20 sacks of cement at 300' through drill pipe, filled with mud to 35' of surface, set bridge at 35' and capped with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H & H Drilling Company

Address P. O. Box 54, Wichita, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
W. H. Duley (employee of owner) ~~operator~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Duley
P. O. Box 544, Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April, 1954

My commission expires April 14, 1956

Sam Council Notary Public.

PLUGGING
FILE SEC 34 24 DLW
BOOK PAGE 24 LINE 41

RECEIVED
STATE CORPORATION COMMISSION
4-7-54
WICHITA, KANSAS
CONSERVATION DIVISION
Wichita, Kansas


CERTIFIED DRILLER'S LOG

COMPANY:	GULF OIL CORPORATION	LEASE:	WANDA #1
CONTRACTOR:	H & H DRILLING COMPANY	LOCATION:	NW NW NW 34-24-12W Stafford County, Kansas
COMMENCED:	3-11-54		
COMPLETED:	4-1-54	CASING RECORD:	696' of 8-5/8", cem. w/350 sacks cement.
ELEVATION:			
POTENTIAL:	D&A		

<u>FORMATION</u>	<u>DEPTH</u>
Clay	0 - 35
Sand	35 - 95
Shale	95 - 285
Sand	285 - 310
Shale	310 - 470
Shale & Shells	470 - 710
Shale	710 - 1455
Shale & Shells	1455 - 1730
Shale & Lime	1730 - 2985
Lime	2985 - 3400
Sand & Shale	3400 - 3450
Shale & Lime	3450 - 3555
Lime	3555 - 3898
Lime & Shale	3898 - 3940
Shale	3940 - 3945
Lime	3945 - 4084
Shale	4084 - 4090
Lime	4090 - 4150
RTD	4150

RECEIVED
STATE CORPORATION COMMISSION
APR 10 1954
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.



R. E. HARTMAN

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 9th day of April, 1954.



Notary Public

My Commission Expires: August 25, 1956

PLUGGING
FILE SEC 34 T 24 R 12W
BOOK PAGE 24 LINE 41