

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. 34 Twp. 24S Rge. (E) 12 (W)

Location as "NE/CNW%SW%" or footage from lines. Center SW NW SW

Lease Owner Gulf Oil Corporation

Lease Name M. S. McMillan Well No. 1

Office Address Box 661 Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-11 19 53

Application for plugging filed 6-14 19 54

Application for plugging approved 6-14 19 54

Plugging commenced 6-15 19 54

Plugging completed 6-22 19 54

Reason for abandonment of well or producing formation Dry Hole.

If a producing well is abandoned, date of last production - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation K.C. Lime Depth to top 3892' Bottom PB3895' Total Depth of Well PB3895' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	700'	None
				5-1/2"	4144'	1962'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PB with sand 3895-3750 and dumped 5 sacks cement at 3750'. After pulling pipe mixed and pumped into 8-5/8" surface pipe, by Halliburton, 20 sacks HOWCOgel mud, HOWCO top cementing plug followed by 100 sacks common cement. Cemented to top.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C. E. Schull Casing Pulling Co.
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
W. H. Duley (employee of owner) or (owner/contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Duley
Box 544 Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of June, 1954

My commission expires April 14, 1956 Notary Public.

24-7368-5 3-53-20M

RECEIVED
STATE CORPORATION COMMISSION
6-30-54
JUN 30 1954
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 34 T 24 R 12W
BOOK PAGE 41 LINE 2

MS

WELL NO. **1** LEASE **N. S. McMillan** COMPANY **Gulf Oil Corporation** A.F.E. **3242**
 DATE—DRILLING BEGAN **10-5-53** WELL COMPLETED **11-11-53** FIRST PRODUCTION
 SAND RECORD **Dry Hole - Temporarily Abandoned**
(Will hold for possible S&W well) TOTAL DEPTH **3095'**
2114'
 INITIAL PRODUCTION

CASING RECORD

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	SACKS CEMENT	LBS. CAL. CHLO.	PULLED	LEFT IN
5-1/8"	30	ST	E	CS	1141'	370			1141'
5-1/8"	34	SR	"	CS	1141'	375			1141'
* 24 jts. Cl. C-1 108 jts. Cl. A									

S-		T-		R-	

REMARKS: ... casing collar.

ELEVATION—

- SET PERFORATED: 1091-96' w/8 shots
- SET PERFORATED: 1096-70' w/8 shots
- " " 1098-1102' w/16 shots
- " " 3052-58' w/24 shots
- " " 3750-51' w/16 shots - acidized
- w/2000 gals. - recalcined w/4000 gals.

FORMATION RECORD:	FROM	TO
sand	0	191
sh		235
red bed		1040
sh		1140
sh, shells		1715
sh, ls		2171
sh		2610
sh, ls		3503
ls		3610
ls, chert		3705
ls		3692
ls, sh		3933
sh		3955
ls		3974
ls, chert		3997
chert		4026
chert, ls		4066
chert, sh		4093
sh, ls		4117
sh, sd		4225
ls		4114

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 12 1954
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 24 T 24 R 12w
 BOOK PAGE 46 LINE 2