


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plot

Stafford County, Sec. 33 Twp. 24 Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE

Lease Owner Nadel and Gussman

Lease Name McMillan

Well No. 1

Office Address 32nd Floor, First National Tower, Tulsa, Oklahoma

74103

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 8 19 75

Application for plugging filed June 8 19 75

Application for plugging approved June 8 19 75

Plugging commenced June 8 19 75

Plugging completed June 8 19 75

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Bieberstein

Producing formation Depth to top Bottom Total Depth of Well 3830

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug @ 250' w/35 sacks cement thru drill pipe.

Top plug @ 40' w/1 sack hulls and 15 sacks cement.

2 sacks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

Address P. O. Box 823, Great Bend, Kansas 67530

STATE OF KANSAS

COUNTY OF BARTON

SO.

Leonard Williamson

(employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Leonard Williamson

P. O. Box 823, Great Bend, Kansas 67530

(Address)

SUBSCRIBED AND SWORN TO before me this 9th

day of

June

19 75

My commission expires April 11, 1978

Marathy M. Hague

Notary Public.

JUN 11 1975

Rec'd
6-11-75

DRILLERS' WELL LOG

DATE COMMENCED: June 2, 1975
DATE COMPLETED: June 8, 1975

Hedel and Gusman
McMILLIAN # 1
C SE of Sec. 33-T24-R12W
Stafford County, Kansas

ELEVATION: 1892 K.B.

0 -	25'	Surface Clay
25 -	164'	Sand
164 -	705'	Red Bed
705 -	721'	Anhydrite
721 -	1730'	Red Bed, Shale, Shells & Salt
1730 -	1886'	Shale, Lime Streaks
1886 -	2165'	Lime, Shale Streaks
2165 -	3145'	Lime and Shale
3145 -	3372'	Lime
3372 -	3378'	Shale
3378 -	3416'	Lime
3416 -	3528'	Shale
3528 -	3546'	Lime and Shale
3546 -	3830'	Lime
	3830'	RTD

FORMATION TOPS

Anhydrite	705
Hoobner	3372
Douglas	3416
Brown Lime	3528
Lansing K.C.	3546
Base K.C.	3830
RTD	3830

SURFACE PIPE: Set 292' of 8 5/8"
28# used pipe w/250 sacks Cement,
2 1/2 Gal, 3 1/2 cc.

AFFIDAVIT

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 9th day of June, 1975.

Christy M. Hague
Notary Public

My Commission Expires: April 11, 1978

JUN 1 1975