

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FORM 4
Rev. 12-15-80
SEP 7 1982
9-7-82
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 4 TWP. 24 RGE. 12 E/W
Location as in quarters or footage from lines:
SW/NW/SE

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Lease Owner Warren American Oil Company
Lease Name Kohrs Well No. #1
Office Address P. O. Box 971 - Midland, Texas 79701
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed _____
Application for plugging filed _____
Plugging commenced August 10, 1982
Plugging completed August 23, 1982
Reason for abandonment of well or producing formation Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation _____ Depth to top _____ bottom _____ T.D. 3900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 291' | NONE |
| | | | | 4 1/2" | 3899' | 3292.10' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 3550' and four (4) sacks cement.
Shot pipe @ 3375'.
Pulled seventy-four (74) joints of 4 1/2" casing.
Squeezed well with four (4) sacks hulls, twenty-five (25) sacks cement, thirty (30) sacks gel, one sack hulls --- released plug --- one hundred twenty-five (125) sacks 50/50 pozmix cement with 4% added gel and 3% calcium chloride.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
JAMES W. ROCKHOLD - Box 698 - Great Bend,
(Address) Ks. 67530

SUBSCRIBED AND SWORN TO before me this 3rd day of Sept, 1982

My Commission expires: 

Margaret Prosser
Notary Public.

KANSAS DRILLERS LOG

COMPANY Warren American Oil Company

SEC. 4 T. 24S R. 12W

FARM Kohrs Unit

NO. 1

LOC. C-SW NW SE

RECEIVED Stafford

ROTARY TOTAL DEPTH 3,900'

COMM. October 28, 1978

COMP. November 5, 1978

CONTRACTOR H-30, Inc. (Rig #7)

NOV 1 1978

ISSUED November 10, 1978

CASING

10 3/4"

8 5/8" Set at 291' cemented w/250 sxs cement

ELEVATION 1,880' K.B.

5 1/2"

4 1/2" Set at 3,899' cemented w/100 sxs cement

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Red Bed 295'

Lime and Shale 427'

Shale and Red Bed 673'

Anhydrite 692'

Shale and Shells 1,427'

Shale 1,794'

Lime and Shale 3,900'

Rotary Total Depth 3,900'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting (Signature)
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 10th day of November, 1978.

Elsie Willison (Signature)
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1982
CONSERVATION DIVISION
Wichita, Kansas

