

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Stafford County. Sec. 2 Twp. 24 Rge. 12 (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW NW SE 1/4

Lease Owner M. B. Armer et al

Lease Name Wm. Hildebrand "B" Well No. 1

Office Address 710 Petroleum Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) oil well

Date well completed July 1948

Application for plugging filed Nov. 19 1950

Application for plugging approved Nov. 19 1950

Plugging commenced Nov. 26 1950

Plugging completed Nov. 26 1950

Reason for abandonment of well or producing formation no production - dry & depleted

If a producing well is abandoned, date of last production Sept. 1949

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Viola Depth to top 3771 Bottom 3904 Total Depth of Well 3985 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	180	none
				5 1/2"	3985	3351

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock to 3760' dumped 5 sax cement at 3760 with dump boiler, top of cement 3725'. Filled with mud to 200 ft. set rock bridge, dumped 15 sax cement, top of cement 140'. Filled with mud to 40' dumped 10 sax cement for cap.

RECEIVED  
STATE CORPORATION COMMISSION  
12-14-50  
DEC 14 1950  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to M. B. Armer  
Address 710 Petroleum Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
L. C. Sponenberg (employee of owner) or owner or operator of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg  
710 Petroleum Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of December, 1950

Hazel Swanton  
Notary Public.

My commission expires Sept. 17, 1951

PLUGGING  
FILE SEC 2-1-24 (NW)  
BOOK PAGE 45 LINE 45

COPY

B & R Drilling, Inc.  
Hildebrand #1

NW SE<sup>1</sup>/<sub>4</sub> of Sec. 2 Twp. 24, Rge. 12  
County: Stafford, Kansas

Total Depth: 3985  
Comm: 6/22/48 Comp: 7/12/48  
Casing  
8 5/8" Set at 180'  
5 1/2" set at 3985

Top Lansing K. C. -3423  
Top Viola -3771  
Top Simpson -3904  
Top Arbuckle -3985  
Cement  
17t Sx - 100 Sx

<u>Formation:</u>	<u>Depth:</u>
Clay	28
Sand - Gravel	65
Shale	80
Sand	136
Shale & shells	181
Red Bed	194
Sand	238
Red Bed	620
Anhydrite	645
Shale	695
Shale & Shells	1148
Salt & Shale	1510
Shale & Shells	1570
Lime	1605
Lime & Shells	1660
Abgtdrute	1720
Sandy lime & Shale	1740
Sand Hard	1785
Shale & Shells	1865
Shale & Lime	1909
Sand Lime	2005
Lime & Shale	2045
Lime	2120
Lime & Shale	2560
Shale	2704
Lime	2745
Shale & Lime	2865
Shale	2970
Lime	3020
Lime & Shale	3060
Lime	3315
Shale & Lime	3408
Lime	3650
Lime & Shale	3771
Viola	3776
Viola Lime	3791
Lime & Chert	3800
Viola & Chert	3825
Lime & Chert	3855
Lime	3905
Shale & Lime	3911
Simpson	3955
Arbuckle Lime	3960
Lime	3970
Arbuckle Lime	3985

**RECEIVED**  
STATE CORPORATION COMMISSION  
DEC 14 1950  
CORPORATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
RUSSELL COUNTY )

**PLUGGING**  
SS FILE SEC 2 T 24 R 12 W  
BOOK PAGE 45 LINE 45

I hereby certify that the above information is true and correct to the best of my knowledge.

(signed) Jane Duncan

Subscribed and sworn to before me this 15th day of July, 1948

(signed) Clara Hummel  
Notary Public

My Comm. Expires 6/17/50