

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.STATE OF KANSAS
STATE CORPORATION COMMISSIONGive All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec. 3 Twp. 24 Rge. 12 NE (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE SW
Lease Owner Huber & Crown Oil Company
Lease Name Bartlett Well No. 1
Office Address 916 S. Pine St. - Pratt, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-20-49 19
Application for plugging filed 1-21-49 19
Application for plugging approved 1-22-49 19
Plugging commenced 1-29-49 19
Plugging completed 2-11-49 19
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough - Great Bend, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4048 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	170'	None
				5 1/2"	3910'	2804'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Lane Wells Plug @ 3882'
Top of Perforations 3830'
Plugged back w/sand 3882 to 3820'
Dumped 5 sacks cement at 3820'
Mud to 170'
Dumped 15 sacks cement on 10' rock bridge
Mud to 30'
10 sacks of cement on top.

RECEIVED
Conservation Div.
2-18-49
FEB 18 1949
STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to J. M. Huber Corporation
Address Box 460 - Pratt, Kansas

STATE OF KANSAS, COUNTY OF PRATT, ss.

J. L. Kyler

(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


(Address)

SUBSCRIBED AND SWORN to before me this 17th day of February, 1949

My commission expires August 20, 1951

Notary Public.

22-2625 2-48-15M



DRILLER'S LOG

COMPANY: HUBER, ET AL
 CONTRACTOR: CROWN OIL COMPANY, INC.
 FARM NAME: No. 1 Bartlett

LOCATION: NE 1/4 SW, 3-24S-12W
 Stafford County, Kansas

COMMENCED: 12-1-48
 COMPLETED: 1-20-49

ELEVATION: 1865
 PRODUCTION: DRY & ABANDONED

CASING USED: 8 5/8" at 170' with 175 sacks.
 5 1/2" at 3910' with 100 sacks.

Collar	4
Clay	20
Sand	50
Sand and Clay	70
Clay	90
Sand	150
Shale-Shells	169
Red Bed	295
Red Shale	655
Lime	680
Shale	775
Shale and Shells	1105
Shale and Shells	1470
Shale and Lime Shells	1610
Lime and Shale	1680
Lime, Shale broken	1750
Lime	2155
Lime and Shale Broken	2265
Lime and Shale	2880
Broken Lime	3045
Lime and Shale	3085
Lime	3125
Lime and Shale Broken	3228
Lime	3290
Shale and Lime	3456
Lime	3745
Lime and Shale	3771
Shale	3807
Shale and Lime	3836
Lime and Chert	3864
Lime	3887
Lime and Chert	3940
Lime and Shale	3965
Shale	3994
Lime	4048
Total Depth	4048

GEOLOGICAL TOPS:

Lansing 3945
 Viola 3830
 3830-51, chert and coarse crystal-
 line limestone in part
 dolomitized, poor spotted
 porosity and trace staining.
 3851-63, dolomite and chert, medium
 fine crystalline, fair por-
 osity in part, fair stain,
 no odor.
 D.S.T. 3834-64, open 1/2 hour, recovered
 180' gassy mud with few
 spots free oil. Bottom
 Hole Pressure 175 1/2 in 10
 minutes.
 3865-71, dolomite medium fine crys-
 talline fair to good por-
 osity in part stained, no
 odor.
 Top Simpson 3948
 Top Arbuckle 3998
 Rotary Total Depth 4048, no shows. Schlumberger.
 5 1/2" at 3910 with 100 sacks. Drilled cement to
 3882, perforated 24/3830-36, set 1 1/2 hours, no
 fluid. Perforated 23/3837-45, very small show
 oil on gun ports 3844-45, shut down 1 hour, no
 fluid, perforated 24/3844-52. Washed hole with
 150 gallons water with casing swab, bailed dry,
 no shows. Dumped 1/2 barrel water on bottom then
 1/2 barrel acid. Let set 2 1/2 hours, bailed dry and
 had rainbow on water, no free oil. Perforated
 24/3851-59, wait 1 hour, no fluid. Dumped 125
 gallons acid on bottom and loaded hole with 1200'
 water, set 1 1/2 hours, swabbed down and had no shows
 500 acid through casing, swabbed down and swabbed
 26 2/3 barrels water plus 4 barrels oil/3 hours.
 Filled up 1000' fluid in hole/2 1/2 hours. Swabbed
 39.9 barrels water plus 1.6 barrels oil/3 hours.
 Shut down 8 hours. Swabbed 45.9 barrels water
 plus 1.16 barrels oil/3 hours. DRY & ABANDONED.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Edward A. Huffman, hereby certify that the above is a true and correct copy of the
 log of the Bartlett No. 1, located in the Northeast Quarter of the Northeast Quarter of the
 Southwest Quarter (NE 1/4 SW) of Section Three (3), Township Twenty-four (24) South, Range Twelve
 (12) West, Stafford County, Kansas.

Edward A. Huffman
 Edward A. Huffman, District Manager
 J. H. HUBER CORPORATION

Subscribed and sworn to before me this 11th day of March, 1949.

Desaith J. Reeves
 Notary Public

My Commission expires January 26, 1953.

PLUGGING
 FILE SEC 3 T 24 R 12
 BOOK PAGE 80 LINE 34