


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Stafford County, Sec. 5 Twp. 24 Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines NE SE SE
Lease Owner The Carl Todd Drilling Company, et al
Lease Name Knoche Well No. 1
Office Address 404 KFH Building
Character of Well (completed as Oil, Gas or Dry Hole) lost hole
Date well completed September 27 1951
Application for plugging filed July 20 1954
Application for plugging approved July 20 1954
Plugging commenced July 24 1954
Plugging completed July 28 1954
Reason for abandonment of well or producing formation lost hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 3816 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	260	
				5 1/2	3807	2200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Drilled to 3026. Lost hole. Mixed and pumped in 20 sacks
Gel Mud and pumped in 70 sacks cement. Stopped plug at
250". Mud and cement by Globe Cementing Company.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Cementing Company
Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Carl Todd (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

404 KFH Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of August, 1954

My commission expires August 31, 1955

Notary Public.
8-3-54

PLUGGING
WILL SEC 5 T24 R12W
BOOK PAGE 49 LINE 26

CONSERVATION DIVISION
WICHITA

THE CARL TODD DRILLING COMPANY

404 KFH Building

Wichita 2, Kansas

The Carl Todd Drilling Company, et al
KNOCKE #1

NE SE SE 5-24-12W

Stafford County, Kansas

Date Commenced: September 13, 1951

Date Completed: September 27, 1951

Elevation: 1880 R.B.

Casing Record:

8-5/8" casing set at 260' with
175 sacks cement

5 1/2" casing set at 3807' with
125 sacks cement

Rotary Tools: 0' to 3816'

LOG

0	160	Surface sand, clay and gravel
160	260	Red Bed and shells
260	670	Red Bed
670	690	Anhydrite
690	1530	Shale and shells
1530	1720	Lime and shale
1720	1765	Lime
1765	1890	Lime and shale
1890	2005	Lime (sandy)
2005	2295	Lime and shale
2295	2350	Broken lime
2350	3230	Lime and shale
3230	3325	Lime
3325	3465	Shale and lime
3465	3655	Lime
3655	3806	Lime and shale
3806	3816	Viola - Rotary T.D.

Formation Tops - R.B.

Heebner Shale	3290
Brown Lime	3437
Lansing	3462 (31582)
Conglomerate	3768
Viola	3804

5 1/2" pipe collapsed @ 3017

Swaged out pipe. Cemented @ 3017 with
125 Sacks. Drilled out to 3026. Lost
hole. Abandon.

I, Carl Todd, do hereby certify that
the above log is correct to the best
of my knowledge and belief.

Carl Todd

