

15-155-20812-00-00

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.
Wichita, KS 67202API Number 15-155-20,812

Operator's Full Name McGinnis Oil Company
 Complete Address 1026 Union Center Bldg., Wichita, Kansas
 Lease Name Swanson Well No. 1
 Location SE SW SW Sec. 1 Twp. 23 Rge. 5 (~~EAST~~) (West)
 County Reno Total Depth 3977'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated

Plugging Contractor Brandt Drilling Co., Inc. and Allied Cementing Co., Inc.
 Address 1200 Douglas Bldg., Wichita, Kansas License No.
 Operation Completed: Hour: 12:30 AM Day: 27 Month: July Year: 1981
 Plugging Operations attended by Agent? All X Part None
 The above well was plugged as follows: 8 3/8" - 805' - 400 sacks circ. (salt mining area)

Hole circulated and Filled with mud, 25 sacks 60-40 Pozmix w/3% Cal. chl. pumped through drill at 800' and let set up for 3 hours.
Hole circulated and Filled to base of cellar with 180 sacks 60-40 Pozmix w/4% gel and 3% cal. chl. Rathole cemented with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG - 3 1981
8-3-81
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Conservation Division AgentDATE 8-26-81INV. NO. 6275-W

12925