

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 86-36
LOCATION NE-NE-NE
SEC. 8 TWP. 24 RGE. 12W

Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 1 Lease Knocke

Operator Northern Pump Co Address Box 317 Great Bend Kans.

Field _____ County Stafford

Total Depth 4038 Feet.

(Describe briefly the manner in which the well was plugged)

8 1/8" 235' Circulated With 200 ss Cement
5 1/2" 4023' Cemented With 150 ss Plugged back Baker
Plug 3700' Perforated 3627'-3624' filled With crushed
rock to 3620' Coarse Rock to 3615' 5 ss Cement to
3575'. Pulled 5 1/2" casing. Pumped 15 ss Yellow
Mud Plug and 70 ss Cement to Base of
Cellar. Pumped by Hoffmeyer & Co. Cementing Co
West Supply Co Pulling Concre (Red)

PLUGGING
FILE SEC. 8 TWP. 24 R. 12W
BOOK PAGE 86 LINE 36

RECEIVED
STATE CORPORATION COMMISSION
3-31-53
MAR 31 1953
CONSERVATION DIVISION

W. A. Rivers
District Conservation Agent
Date 3-28-53