

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONJAN 6 1964
1-6-64
CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name Rex & Morris Drilling Co.Complete Address: P. O. Box 334, El Dorado, Kansas 67042Lease Name Reid Well No. # 1Location SW SW NW Sec. 22 Twp. 24 Rge. 12 (E) (W) WCounty Stafford Total Depth 3956Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Comstock Pipe Pulling Inc.Address: Stafford, Kansas License No. 490Operation Completed: Hour 9:00AM Day 3rd Month Jan. Year 1964

The Above well was plugged as follows:

237' of 8 5/8" surface pipe, cemented with 180 sacks. 3905' of 5 1/2" long string, cemented with 100 sacks. Plug back to 3700'. Top perforation 3682', Bottom of hole sanded to 3670', and cemented with 5 sacks. Fluid was up in hole, and would not bail down. Plug was pushed to 250', 10' rock bridge. 6 sacks of cement was mixed in barrel and put on plug through dump bailer, and let set over night. Next morning hole bailed down and 20 sacks cement was added to plug. Hole was filled with mud to 40', 10' rock bridge, cemented with 10 sacks to base cellar. 3126' of 5 1/2" long string was recovered from the hole

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 1/7/64
INV. NO. 8424-11