

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

15-051-19513-00-01

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

D&A Sept. 1950 by Jones, Shelburne & Farmer
API # washed down 1961 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Diehl Oil, Inc. KCC LICENSE # 09346
(owner/company name) (operator's)

ADDRESS P. O. Box 234 CITY Hays

STATE KS ZIP CODE 67601 CONTACT PHONE # (913) 625-6711

LEASE Ruder "D" WELL# 1-A SEC. 8 T. 15 R. 18 (East/West)

SE - NE - SE - SPOT LOCATION/QQQQ COUNTY Ellis

1650 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL ☐ GAS WELL ☐ D&A ☐ SWD/ENHR WELL ☒ DOCKET# C-8781

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8" SET AT 146' CEMENTED WITH 150 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 3738' CEMENTED WITH 125 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: DV tool @ 1160' w/400 sacks

ELEVATION 1992 KB T.D. 3827' PBSD ANHYDRITE DEPTH 1159'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD ☐ POOR ☐ CASING LEAK ☐ JUNK IN HOLE XX

PROPOSED METHOD OF PLUGGING Emergency plugging. Tubing parted @ 958'. Got down to 1197'. Ran in tubing to 1130'. Pumped 200 sacks class A, 200 sacks 65/35 poz 2 hulls, 150 sacks 65/35 poz 2 hulls max psi 500#. Unable to pull out tubing.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACO-1 FILED? yes

If not explain why? No well logs run on this hole.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Glenn D. Diehl PHONE# (913) 625-6711

ADDRESS P. O. Box 234 City/State Hays, KS 67601

PLUGGING CONTRACTOR BJ Services KCC LICENSE #

(company name) (contractor's)

ADDRESS 1707 East 10th Hays, KS 67601 PHONE # (913) 625-3019

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged 6-9-92

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6/18/92 AUTHORIZED OPERATOR/AGENT: [Signature]

(signature)

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1992
6-22-92
CONSERVATION DIVISION
Wichita, Kansas

Backoffed tubing. Lost 16 joints in hole. Recovered 21 joints. Squeeze with 50 sacks 65/35 poz max pressure 100# shut in @ 50#.