

2 090032

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 155-21,003-0000

NESWSE, SEC. 24, T 23 S, R 5 W/EX

990 feet from N/S section line

1650 feet from W/E section line

Lease Name BONTRAGER Well # 1

County Reno

Well Total Depth 3920 127.40 feet

Conductor Pipe: Size 10 3/4 feet 331

Surface Casing: Size 8 5/8 feet 718

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Operator: N.C.A.R.

Name & Address Box 6

Great Bend, Ks.

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kaw Drilling License Number 6739

Address \_\_\_\_\_

Company to plug at: Hour: 4:00p.m. Day: 8 Month: 8 Year: 19 84

Plugging proposal received from \_\_\_\_\_

(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: 35 sacks at 770'; 25 sacks at 350'; 25 sacks and wood & rubber plug at 50'  
10 in rat 5 in water well

K.C.C. \_\_\_\_\_ Plugging Proposal Received by Ron Wilson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:00p.m. Day: 8 Month: 8 Year: 1984

ACTUAL PLUGGING REPORT filled hole with heavy drilling mud; run drill pipe to 770';  
spotted 35 sacks cement through drill pipe; pulled drill pipe to 350'; spotted 25 sacks  
cement through drill pipe; pulled drill pipe to 50'; spotted 25 sacks cement on top of a  
wood and rubber plug through drill pipe; run one joint of drill pipe in rat hole cir-  
culated 10 sacks cement to surface; circulated 5 sacks cement to surface in water well

Remarks: Halliburton Ticket #749108  
(If additional description is necessary, use BACK of this

RECEIVED  
STATE CORPORATION COMMISSION

APR 15 1984  
8-15-84  
CONSERVATION DIVISION  
WICHITA, KANSAS

Signed Dave Weitz  
(TECHNICIAN)

INVOICED

DATE 8-16-84

INV. NO. 3217