

1 010060

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,755-60-60

C SW NW SE, SEC. 31 , T 29 S, R 14 (W/E)

1650 feet from (S) section line

2310 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4736

Lease Name Howell Well # 1

Operator: R. S. Howell, Inc.

County Pratt

Name & Address 619 South Iowa

Well Total Depth 4705 Simpson 152 91 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address P. O. Box 982, Pratt, KS 67124

Company to plug at: Hour: 2:50 pm Day: 20 Month: December Year: 19 85

Plugging proposal received from Scott Mason

(company name) Aldebaran (phone) 316-672-7471

Elevation N/A

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite N/A

1st plug in the Arbuckle with 50 sx cement if 50' or more

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug at 370' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement. Plugging Proposal Received by James R. Kapp

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:30 pm Day: 20 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 860' with 50 sx cement, 2nd plug at 380' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement. 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel
(If additional description is necessary, use BACK of this form.)

RECEIVED

INVOICED

DATE DEC 27 1985

INV. NO. 11741

DEC 27 1985
12-27-85
CONSERVATION DIVISION
Wichita, Kansas

Signed James R. Kapp
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 12 month 14 day 1985 year

API Number 15- 151-21,755-00-00

OPERATOR: License # 4736
Name R. S. Howell, Inc.
Address 619 S. Iowa
City/State/Zip Pratt, Kansas 67124
Contact Person Robert S. Howell
Phone 316-672-5142

C. SW NW SE Sec. 31, Twp. 29 S, Rg. 14
1650 Ft. from South Line of Section
2310 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5829
Name Aldeheran Drilling Co., Inc.
City/State Pratt, Kansas 67124

Nearest lease or unit boundary line 330 feet
County Pratt
Lease Name Howell Well # 1
Ground surface elevation not staked feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Surface pipe by Alternate: 1 X 2
Depth to bottom of fresh water 150 ft.
Depth to bottom of usable water 200 ft.
Surface pipe planned to be set 350
Projected Total Depth 4700 feet
Formation Simpson

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
cementing will be done immediately upon setting production casing.
Date 12-9-85 Signature of Operator or Agent Robert S. Howell Title President

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. 2
This Authorization Expires 6-9-86 Approved By 12-9-85

Handwritten notes: 4900', 350' 48 5/8, 1 plug, available 50' ref, 2 Bar, available 50' ref, 3 378', plug 40' SB + 10' ref, 10' ref, 10' ref, RECEIVED STATE CORPORATION COMMISSION

Vertical handwritten note: pump water from farm well

DEC 27 1985