

2 060020 #45-015-21681

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER ~~15-015-21251~~  
S.E. SW  
NE, SEC. 34, T. 27S, R. 5 W/E

R

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5199

OPERATOR: Jimmy RAZOOK Oil Co.  
NAME &  
ADDRESS R.R. 4 Box 102  
Augusta, KS

\_\_\_\_\_ FEET FROM N/S SECTION LINE

\_\_\_\_\_ FEET FROM W/E SECTION LINE

LEASE NAME Fleming A Well # 3

COUNTY Butler

WELL TOTAL DEPTH 2750' 89.38 FEET

CONDUCTOR PIPE: SIZE 5 1/2 FEET 2749

SURFACE CASING: SIZE 8 5/8 FEET 200'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR B & S Well Service LICENSE NUMBER 6013

ADDRESS 608 W 8th Winfield KS

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: 14 MONTH: 10 YEAR: \_\_\_\_\_

PLUGGING PROPOSAL RECEIVED FROM Dale Smith

(COMPANY NAME) ABOVE (PHONE) \_\_\_\_\_

RECEIVED  
NOV 12 2004

KCC WICHITA

WERE: As Tubing Parted At Approx 1990' Would Pump 75 5x5  
Com Cement & Displace W-R. Wiper Plug to 1990' & Dump 5 5x5  
Sand on Plug. Pump 3 hulls 666's 100 5x5 Com 37cc Down  
Surface Pipe.

PLUGGING PROPOSAL RECEIVED BY Dust off  
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 2:35 PM DAY: 14 MONTH: 10 YEAR: 19 83

ACTUAL PLUGGING REPORT Hally Burton Displaced 75 5x5 Com Cement to  
1990' with Wood Rubber plug & Dumped 5 5x5 Forc Sand on Plug.  
Shot & pulled 1226' 5 1/2 casing.

Hally Burton Pumped 3 5x5 hulls 666's Gel & 100 5x5 Com  
Cement with 37cc Down 8 5/8" Then Swedge.

P.I.P 600# S.T.P. 300#

REMARKS: Ticket # 516 593